# Conditions of Service and Tariff December 1, 2023

Amended document
[Article 14.5.2] as of December 5, 2023
[Article 15.1.2.1] as of January 1, 2024
[Articles 4.3.5, 4.3.5.1, 4.3.5.2, 4.3.5.3, 10.4, 11.1.3.5, 11.1.3.5.4, 11.2.3.3.1 et 11.2.3.3.2] as of January 29, 2024

An electronic version of this document is available at Energir.com/conditions-tariff-en

# **INTRODUCTORY NOTE**

The content of the present document has been set by the Régie de l'énergie pursuant to the *Act Respecting the Régie de l'énergie* (R.S.Q., c. R-6.01). Any customer who disagrees with the application of the present document by the distributor may submit a complaint to the distributor in accordance with the complaint review procedure established by the distributor and approved by the Régie de l'énergie in Decision D-98-25, File R-3392-97, May 13, 1998, Appendix M. If the customer does not agree with the distributor's decision concerning its complaint, it may then ask the Régie to review it in accordance with the provisions of Chapter 7 of the aforementioned Act (Sections 86 to 101).


# **TABLE OF CONTENTS**

SECT	ION I - APPLICATION	<b>7</b>
1.	APPLICATION	8
1.1	Application	8
1.2	Information	8
1.3	Definitions	8
SECT	ION II - CONDITIONS OF SERVICE	13
2.	DISTRIBUTION SYSTEM	14
2.1	Distribution System	
2.1.1 2.1.2		
3.	SERVICES	15
3.1	Natural Gas Services	15
3.2	Choice of Services	15
4.	NATURAL GAS SERVICE REQUEST AND CONTRACT	16
4.1	Natural Gas Service Request	16
4.1.1		
4.1.2 4.1.3		16 16
4.2	Information to be Provided for Natural Gas Service Request	
4.2.1	Individual	17
4.2.2		
4.3	Service Connection	
4.3.2	connection Charges	18
4.3.3 4.3.4	<b>-</b>	18 18
4.3.5		
4.4	Lead Times Required by the Distributor to Provide Natural Gas Distribution Service	
4.4.1 4.4.2		
4.5	Form, Formation and Effective Date of Contract	
4.5.1	Form	20
4.5.2		
4.6	Confirmation of Acceptance of the Natural Gas Service Request	
4.7	Contract Term	
4.8	Contract Amendment	
4.9	Contract Termination Written Contract.	
4.9.1		
4.10	Force Majeure	22
4.11	Changes to Conditions of Service and Tariff	22
<b>5.</b>	MEASUREMENT	23
5.1	Metering Devices	23
5.1.1	Metering Device belonging to the Distributor	23
5.1.2	Location of and Access to the Metering Device	23

5.1.3	Metering Device belonging to the Customer	23
5.2	Measurement of Volume of Natural Gas Withdrawn or Injected	. 23
5.3	Reading of Metering Device	
5.3.1	Reading by the Distributor	
5.3.2 5.3.3	Frequency of Readings	
5.4	Volume of Natural Gas Withdrawn or Injected by the Customer	
5.5	Defective Metering Device	
3.3	Defective Metering Device	. 2
6.	BILLING	25
6.1	Billing Methods	25
6.1.1	Volume of Natural Gas Billed	
6.1.2	Contractual Obligations	25
6.1.3 6.1.4	Correction of Error	
6.2	Bills	
6.2.1	Issue	
6.2.2	Transmittal	26
6.2.3 6.2.4	Delivery Information Appearing on the Bill	
0.2.4	Thiornauon Appearing on the bill	20
<b>7.</b>	PAYMENT	28
7.1	Due Date	28
7.2	Terms	
7.2.1	Payment Methods	
7.2.2	Compensation Prohibition	
7.2.3	Equal Payments Plan	28
7.3	Liability	
7.3.1	Written Contract	
7 3 2	Other Contract	20
7.3.2	Other Contract	29
7.3.2 <b>8.</b>	Other Contract  DEPOSIT	
8.	DEPOSIT	30
		<b>30</b>
<b>8.</b> 8.1	DEPOSIT  Requirement  Domestic Use  Other Uses and Customers Subject to Rate D <sub>R</sub>	30 30 30
8.1 8.1.1 8.1.2 8.2	DEPOSIT  Requirement  Domestic Use  Other Uses and Customers Subject to Rate D <sub>R</sub> Amount	30 30 30
8.1 8.1.1 8.1.2 8.2 8.2.1	DEPOSIT  Requirement  Domestic Use  Other Uses and Customers Subject to Rate D <sub>R</sub> Amount  Domestic Use	30 30 30 31
8.1 8.1.1 8.1.2 8.2	DEPOSIT  Requirement  Domestic Use  Other Uses and Customers Subject to Rate D <sub>R</sub> Amount	30 30 30 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2	DEPOSIT  Requirement  Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount  Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub>	30 30 30 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3	Requirement  Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount  Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub>	30 30 30 31 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4	Requirement Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub> Payment  Retention Period	30 30 31 31 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3	Requirement  Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount  Domestic Use Other Uses. Customers Subject to Rate D <sub>R</sub> Payment  Retention Period.  Interest on Cash Deposit.	30 30 31 31 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5	Requirement Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub> Payment  Retention Period	30 30 31 31 31 31
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1	Requirement Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub> Payment  Retention Period.  Interest on Cash Deposit Interest Rate	30 30 31 31 31 32 32
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1	Requirement Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub> Payment  Retention Period  Interest on Cash Deposit Interest Rate Payment of Interest.  Use or Return to the Customer Use of the Deposit	30 30 31 31 31 32 32 32 32
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6	Requirement Domestic Use Other Uses and Customers Subject to Rate DR  Amount Domestic Use Other Uses Customers Subject to Rate DR  Payment  Retention Period.  Interest on Cash Deposit Interest Rate. Payment of Interest.  Use or Return to the Customer	30 30 31 31 31 32 32 32 32
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1	Requirement Domestic Use Other Uses and Customers Subject to Rate D <sub>R</sub> Amount Domestic Use Other Uses Customers Subject to Rate D <sub>R</sub> Payment  Retention Period  Interest on Cash Deposit Interest Rate Payment of Interest.  Use or Return to the Customer Use of the Deposit	30 30 31 31 31 32 32 32 33
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6.1 8.6.2	Requirement Domestic Use Other Uses and Customers Subject to Rate DR  Amount Domestic Use Other Uses Customers Subject to Rate DR  Payment Retention Period.  Interest on Cash Deposit Interest Rate. Payment of Interest.  Use or Return to the Customer Use of the Deposit Return of the Deposit Return of the Deposit Return of the Deposit	30 30 31 31 32 32 32 33 33
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1 8.6.2	DEPOSIT  Requirement Domestic Use Other Uses and Customers Subject to Rate DR  Amount Domestic Use Other Uses Customers Subject to Rate DR  Payment  Retention Period  Interest on Cash Deposit Interest Rate Payment of Interest Use or Return to the Customer Use of the Deposit Return of the Deposit Return of the Deposit Return of the Deposit  COLLECTION  Payment Agreement	30 30 31 31 32 32 32 33 33
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6.1 8.6.2	Requirement Domestic Use. Other Uses and Customers Subject to Rate DR.  Amount Domestic Use. Other Uses. Customers Subject to Rate DR.  Payment Retention Period.  Interest on Cash Deposit. Interest Rate. Payment of Interest. Use or Return to the Customer Use of the Deposit. Return of the Deposit. Payment Agreement Payment Default.	30 30 31 31 31 32 32 32 33 33
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1 8.6.2 9.1 9.2 9.3	Requirement Domestic Use Other Uses and Customers Subject to Rate DR Amount Domestic Use Other Uses. Customers Subject to Rate DR Payment Retention Period.  Interest on Cash Deposit Interest Rate. Payment of Interest. Use or Return to the Customer Use of the Deposit. Return of the Deposit. Return of the Deposit Return of the Deposit Return of the Deposit Return Default Late Payment Charge.	30 30 31 31 32 32 32 33 33 33
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1 8.6.2  9.1 9.2 9.3 9.4	Requirement.  Domestic Use. Other Uses and Customers Subject to Rate DR.  Amount.  Domestic Use. Other Uses. Customers Subject to Rate DR.  Payment.  Retention Period.  Interest on Cash Deposit. Interest Rate. Payment of Interest.  Use or Return to the Customer Use of the Deposit. Return of the Deposit. Return of the Deposit. Return of the Deposit. Return Default.  Late Payment Charge.  Collection Procedures.	30 30 31 31 32 32 32 33 34 34 34 34
8.1 8.1.1 8.1.2 8.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 9.1 9.2 9.3 9.4 9.4.1	PEPOSIT  Requirement  Domestic Use Other Uses and Customers Subject to Rate DR  Amount  Domestic Use Other Uses. Customers Subject to Rate DR  Payment  Retention Period  Interest on Cash Deposit  Interest Rate. Payment of Interest  Use or Return to the Customer  Use of the Deposit  Return of the Deposit  COLLECTION  Payment Agreement  Payment Default  Late Payment Charge  Collection Procedures  Collection Procedures  Collection Notices	30 30 31 31 32 32 32 33 34 34 34 34 34
8.1 8.1.1 8.1.2 8.2 8.2.1 8.2.2 8.2.3 8.3 8.4 8.5 8.5.1 8.5.2 8.6 8.6.1 8.6.2  9.1 9.2 9.3 9.4	Requirement.  Domestic Use. Other Uses and Customers Subject to Rate DR.  Amount.  Domestic Use. Other Uses. Customers Subject to Rate DR.  Payment.  Retention Period.  Interest on Cash Deposit. Interest Rate. Payment of Interest.  Use or Return to the Customer Use of the Deposit. Return of the Deposit. Return of the Deposit. Return of the Deposit. Return Default.  Late Payment Charge.  Collection Procedures.	30 30 31 31 32 32 32 33 33 33 33 34 34 34

SECT	ION III - TARIFF	36
10.	OPTIONS AVAILABLE TO CUSTOMERS	37
10.1	Service Options	37
10.2	Combination of Customer's and Distributor's Services	
10.2	Combinations of Services	
10.4	Customer Grouping	
10.4		
11.	SUPPLY	39
11.1	Distributor's Service	
	.1 Application	
	.2 natural gas Supply Rate	
11.2	Customer-Provided Service	42
11.2.	.1 Application	42
11.2.		
	.3 Terms and Conditions	
11.3	Make-Up Gas Service	
	.2 Rate	
11.3.	.3 Terms and Conditions	47
11.4	Contribution to greening the gas system	
11.4.	.1 Application	48
11.4.	.2 Rate for Contribution to greening the gas system	48
<b>12.</b>	TRANSPORTATION	49
12.1	Distributor's Service	49
	.1 Application	
12.1.		
12.1. 12.1.	.3 Minimum Annual Obligation (MAO)	
12.2	Customer-Provided Service	
	.1 Application	
	.2 Rate	
12.2.	.3 Terms and Conditions	51
<b>13</b> .	LOAD BALANCING	52
13.1	Distributor's Service	
	.1 Application	
13.1. 13.1	.2 Load-BalAncing Rate	
13.1.		
13.1.	3	
13.1.		
13.2 13.2.	Customer-Provided Service	
	.2 Rate	
13.2.	.3 Terms and Conditions	57
<b>14.</b>	DISTRIBUTION	58
14.1	General Provisions	58
14.1.		
14.1.		
14.1. 14.1.	.3 Contract Term	
14.1.	· ·	
14.2	Distribution Service D <sub>1</sub> : General	
	.1 Application	58
14.2.	.2 Distribution Rate D <sub>1</sub>	58

	Rate Rebates	
	Distribution Services D3 and D4: Stable Load	
14.3.1	Application	
14.3.2	Distribution Rates D₃ and D₄	61
14.3.3	Contract Extension	
14.3.4	Revision of Subscribed Volume	
	Distribution Service D <sub>5</sub> : Interruptible	
	Application	
14.4.2 14.4.3	Minimum Annual Obligation (MAO)	
14.4.4	Competition Rate Adjustment	
14.4.5	Combination of Rates D <sub>3</sub> and D <sub>5</sub> or D <sub>4</sub> and D <sub>5</sub>	66
14.4.6	Interruptions	66
14.4.7	Contract Extension	67
14.5	Receipt Service D <sub>R</sub>	
14.5.1	Application	
	Receipt Rate	
14.5.3 14.5.4	Contract Renewal and Indemnity	
14.5.5	Revision of Maximum Contractual Capacity (MCC)	
14.5.6	Daily Overruns of Maximum Contract Capacity (MCC)	
14.5.7	Possession and Control	
14.5.8	Request for Nomination	
14.5.9	Simultaneous Injection to the Same Receipt Point	69
	CAP-AND-TRADE EMISSION ALLOWANCES SYSTEM	
	Distributor's Service	
	Application	
	Customer-Provided Service	
	Applications	/()
<b>16</b> .		70
	OTHER APPLICABLE CHARGES	70
16.1.1	Distribution System Connection Charge	7071
16.1.2	Distribution System Connection Charge	707171
16.1.2 16.1.3	Distribution System Connection Charge	<b>7</b> 0 <b>71</b> 7171
16.1.2 16.1.3 16.1.4	Distribution System Connection Charge	707171717171
16.1.2 16.1.3 16.1.4 16.1.5	Distribution System Connection Charge	70717171717171
16.1.2 16.1.3 16.1.4	Distribution System Connection Charge	7071717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7	Distribution System Connection Charge	707171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8	Distribution System Connection Charge	707171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8	Distribution System Connection Charge	7071717171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8 SECTION	Distribution System Connection Charge	7071717171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8 SECTION	Distribution System Connection Charge	70717171717171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8 SECTI	Distribution System Connection Charge Charge for Non-Standard Connection Charge for Reduction of Connection Time Charge Following Request to Verify a Metering Device Charge for Non-Honoured Payment Late Payment Charge Collection Charge Reconnection Charge Reconnection Charge  The FFECTIVE DATE AND TRANSITIONAL PROVISIONS EFFECTIVE DATE AND TRANSITIONAL PROVISIONS  Effective Date Application	707171717171717171717171717171
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8 SECTION 17.1 17.1 17.1.1	Distribution System Connection Charge Charge for Non-Standard Connection Charge for Reduction of Connection Time. Charge Following Request to Verify a Metering Device. Charge for Non-Honoured Payment. Late Payment Charge Collection Charge Reconnection Charge.  CON IV - EFFECTIVE DATE AND TRANSITIONAL PROVISIONS EFFECTIVE DATE AND TRANSITIONAL PROVISIONS Effective Date Application.  Transitional Provisions	7071
16.1.2 16.1.3 16.1.4 16.1.5 16.1.6 16.1.7 16.1.8 SECTION 17.1 17.1 17.1 17.2 17.2.1	Distribution System Connection Charge Charge for Non-Standard Connection Charge for Reduction of Connection Time Charge Following Request to Verify a Metering Device Charge for Non-Honoured Payment Late Payment Charge Collection Charge Reconnection Charge Reconnection Charge  The FFECTIVE DATE AND TRANSITIONAL PROVISIONS EFFECTIVE DATE AND TRANSITIONAL PROVISIONS  Effective Date Application	70717171717171717171717171717171717171



# 1. APPLICATION

#### 1.1 APPLICATION

The provisions hereof establish the conditions of service and rates of Énergir, s.e.c. (the distributor) in its exclusive distribution territory.

#### 1.2 Information

The distributor shall inform its customers of these conditions of service and the application of various services and rates. In addition, when new conditions of service or rates come into effect, the distributor shall inform its customers of them in writing. It shall also inform them of the availability of different rates, of their right to avail themselves of the most advantageous Distribution Rate and to obtain free of charge copy of the *Conditions of Service and Tariff*.

#### 1.3 **DEFINITIONS**

In this document, the following terms shall have the meaning ascribed to them:

#### **AGREED DELIVERY POINT**

Physical or geographical location where natural gas is delivered:

- to the distributor, at a point specified in the customer-provided natural gas supply service contract agreement; or
- within the territory on Énergir's gas system or outside the territory (ex-territory) at a point specified at the time of the commitment to the nominated volume by a customer subject to Rate D<sub>R</sub>.

#### **BILLING ADDRESS**

Address to which the customer's bill is sent.

#### **CONNECTION**

Connection of a new service address to the distribution system.

#### **CONNECTION PIPELINE**

Underground line belonging to the distributor connecting the distribution main to the connection point at the service address.

#### **CONNECTION POINT**

Point where the distributor's connection pipeline joins connects to the customer's pipes at the service address.

#### **CONSUMPTION ZONE**

Geographic zone extending from the point of interconnection with the TCPL/TQM system delimiting the portion of Énergir's system connected to that interconnect point.

#### **CONTRACT**

Agreement between a customer and the distributor for one or more natural gas services supplied by the distributor to a service address.

#### **CONTRACT PERIOD**

Period of one year or less between two agreed upon dates.

#### **CONTRACT YEAR**

Period of 12 months beginning on the date agreed upon in the written contract.

#### **CUBIC METRE OF NATURAL GAS (m³)**

Quantity of natural gas contained in one cubic metre at an absolute pressure of 101.325 kilopascals and at a temperature of 15 degrees Celsius.

#### **CUSTOMER**

Any individual or legal person, partnership or body that has entered into a contract with the distributor.

#### **CUSTOMER DELIVERY POINT**

Point, immediately after the distributor's metering device, at which the distributor makes the natural gas available to the customer.

#### **CUSTOMER GROUPING**

Customers who form a group to purchase services provided for in the Conditions of Service and Tariff.

#### DAY

Unless otherwise specified, a 24-hour period beginning at 10:00 a.m. Eastern Standard Time (ET), in the absence of an agreed time.

#### **DISTRIBUTION SYSTEM**

Natural gas distribution system as provided in the Act Respecting the Régie de l'énergie. (R.S.Q., c. R-6.01).

#### **DOMESTIC USE**

Utilization of the natural gas service for applications related exclusively to the occupation of a personal residence or of apartments in a housing cooperative or non-profit housing organization, or to the use of common areas in a condominium.

#### **EMITTER**

A person or a municipality qualifying as an emitter within the meaning of Article 2 of the *Regulation respecting a cap-and-trade system for greenhouse gas emission allowances* (chapter Q-2, R. 46.1) and having completed and transmitted to Energir an initial declaration indicating that it is an emitter within the meaning of section 2 of said Regulation.

#### **FIRM SERVICE**

Uninterrupted natural gas service.

#### **FIXED-PRICE SUPPLY AGREEMENT**

Supply service from a specific supplier chosen by the customer, allowing the latter to set the price of the traditional natural gas or the gas from renewable sources supply for a given period, given the agreed-upon price with the supplier to Énergir and taking into consideration the customer's consumption.

#### **GAS FROM RENEWABLE SOURCES**

Has the meaning assigned to it in the Act respecting the Régie de l'énergie.

#### **GROSS HEATING VALUE**

The total number of joules produced by the full combustion, at a constant pressure, of one cubic metre of natural gas in contact with air, under conditions such that the natural gas is free of water vapour; that the natural gas, air and combustion products are at normal temperature, and that all water produced by the combustion is condensed to a liquid state.

#### **INVENTORY**

Natural gas supply and transportation held in inventory by the distributor and necessary for serving the customer during the contract year.

#### **LOAD FACTOR**

Ratio of average annual daily load to peak daily load.

#### **METERING DEVICE**

Any device or combination of devices used to measure the natural gas withdrawn or injected by the customer, including in particular a meter, with or without a remote reading device, or a chromatograph.

#### **METERING POINT**

One metering device, or more than one if the distributor deems appropriate to use more than one, measuring the natural gas withdrawn by a single customer and serving one or more buildings or facilities located at a single site occupied by that customer or measuring the natural gas injected by a customer.

#### **MINIMUM ANNUAL OBLIGATION (MAO)**

It can either be:

- A minimum annual volume of natural gas, for each contract year, that a customer agrees to pay for, in
  accordance with the Conditions of Service and Tariff, whether or not it withdraws or injects the natural gas;
  or
- A minimum income, for each tariff year, that the customer undertakes to pay, in accordance with the text of the Conditions of Service and Tariff.

#### **MULTIPLIER FACTOR**

The coefficient applied to the measurement of the volume of natural gas withdrawn or injected by a customer, in order to take account of the characteristics of the metering device.

#### **NATURAL GAS SERVICE**

One or more of the distributor's following services: natural gas supply service, transportation service, load-balancing service and distribution service.

#### **NATURAL GAS**

Has the meaning assigned to it in the Act of the Régie de l'énergie and includes gas from renewable sources as define in the Act of the Régie de l'énergie.

#### **NOMINATED VOLUME**

Volume the customer agrees to inject in the distribution network during a day at an agreed delivery point.

#### **NORMALIZED ANNUAL CONSUMPTION**

Average annual volume of the last 24 months after normalization.

#### **NORTHERN ZONE**

The Abitibi-Témiscamingue region served by the distributor.

#### **PAYMENT AGREEMENT**

Agreement between a customer and the distributor to spread the payment of unpaid amounts owing on the due date over a period of time and to provide for full payment of the bills issued during the period covered by the agreement.

#### PERCENTAGE OF GAS FROM RENEWABLE SOURCES PRESCRIBED BY THE REGULATION

Percentage of gas from renewable sources that Énergir must deliver as defined in the *Regulation respecting the* quantity of gas from renewable sources that must be delivered by a distributor.

#### **PRESSURE FACTOR**

The coefficient applied to the measurement of the natural gas volume withdrawn or injected by a customer in order to take account of atmospheric pressure and delivery pressure.

#### **PRICE OF NATURAL GAS TRADED AT IROQUOIS**

Price of natural gas according to the "Daily price survey" indicator published by Platts in Gas Daily under "Canadian Gas: Iroquois, receipts; Midpoint; Flow Date(s)."

#### **RECEIPT POINT**

Physical location where producers' facilities connect to Énergir's connection pipelines to move natural gas to the gas system.

#### **RECOGNIZED MARGINAL REDUCTION**

When a customer participates in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), the recognized marginal reduction is evaluated by calculating the difference between the typical consumption following the implementation of a higher-efficiency measure and the consumption following the implementation of a standard measure. This recognized marginal reduction and the period for which it will be recognized will be included in the contract documents governing the customer's participation in the energy efficiency program.

#### **SERVICE ADDRESS**

Address that is or will be connected to the distribution system, including the receipt point.

#### **SOUTHERN ZONE**

The territory served by the distributor with the exception of the Northern zone.

#### **TARIFF**

The schedule of rates and rate conditions applicable to the customer and the distributor, as set out in Sections III and IV.

#### **TCPL/TOM TRANSPORTATION**

Transportation of natural gas within Énergir's territory between different consumption zones or outside Énergir's territory, via the TCPL/TQM transmission system.

#### **TRADITIONAL NATURAL GAS**

Refers to natural gas, excluding gas from renewable sources as defined in the Act of the Régie de l'énergie.

#### **UNAUTHORIZED WITHDRAWALS DURING INTERRUPTIONS**

All natural gas withdrawals at a service address not respecting the terms of the interruption notice issued by the distributor under Article 14.4.6 (4°).

#### **VOLUME DEFICIT**

Portion of the minimum volume not withdrawn by a customer.

#### **VOLUMES DELIVERED OUTSIDE THE TERRITORY**

Delivery of natural gas to a point of interconnection with the TCPL/TQM system.

#### **VOLUMES DELIVERED WITHIN THE TERRITORY**

Delivery of natural gas to Énergir's entire system.

#### WITHDRAWALS EXEMPT FROM THE CAP-AND-TRADE EMISSION ALLOWANCES SYSTEM SERVICE

The volumes of natural gas exempted from the cap-and-trade emission allowances system (CTEAS) service are those prescribed by the *Regulation respecting a cap-and-trade system for greenhouse gas emission allowances*.

To be exempted from the CTEAS service, these volumes must have been declared by the emitter in declarations received by the distributor no later than the third working day following the end of the month covered by the billing and as confirmed, at the end of each applicable calendar year, no later than January 31 of each year by sworn statement by the emitter, or if the emitter is a legal entity or a corporation, by an authorized officer thereof;


Also exempted are the volumes of natural gas withdrawn by an emitter and declared in a sworn statement submitted to the distributor no later than January 31 of each year, or if the customer is a legal entity or a corporation, by an authorized officer.

For the above volumes to be exempted from the CTEAS service, the aforementioned declarations must be approved by the Distributor's greenhouse gas (GHG) emissions auditor and the minister of Sustainable Development, Environment and the Fight against Climate Change (or its successor). It is understood that the CTEAS service applicable will be charged to the client if the auditor or the minister (or its successor) were to dismiss the client's declarations.

Notwithstanding the above, also exempted from the CTEAS service are the volumes of gas from renewable sources withdrawn.

#### **WORKING DAY**

Monday to Friday with exception of public holidays.



# 2. DISTRIBUTION SYSTEM

# 2.1 DISTRIBUTION SYSTEM

The distributor shall determine the location of its distribution system, which includes the receipt point.

The distributor shall own the distribution system and shall supply, install, operate and maintain the distribution system up to the connection point or the receipt point.

No one other than the distributor or its authorized agent may at any time or in any way modify or alter its distribution system.

#### 2.1.1 ACCESSIBILITY

The customer shall make the distribution system accessible to the distributor at any time and shall maintain the premises in a manner that permits the distributor to operate the distribution system in accordance with the applicable legislation.

When the customer refuses access to the distribution system of the distributor, the distributor shall send a written notice advising the customer of the intention to proceed to an interruption. The notice must be of at least 10 working days. At the expiration of the notice, the distributor may interrupt natural gas service.

After an interruption of service under this Article, the distributor invoices the reconnection charge set out in Article 16.1.8 to the customer upon the reconnection of the service.

#### 2.1.2 RELOCATION OR MODIFICATION

A person who requests a relocation or modification of the distribution system must be the owner of the property where the service address is located or declare and warrant having, for this purpose, all the authorizations and permissions required from the owner of the premises. The applicant shall provide the distributor, upon request, with any evidence so attesting.

If the distributor relocates or modifies its distribution system following a request made under the preceding paragraph, the distributor will bill the applicant for the cost of work. The cost of work is determined based on the distributor's estimate, the details of which shall be provided to the applicant in advance, or on the actual cost of work. The method of billing the cost of work shall be determined when the relocation or modification request is made.

If a request to relocate or modify the distribution system is withdrawn, the distributor may bill the applicant if work has already been undertaken or completed. The amount shall then be based on the actual cost of work.

# 3. SERVICES

# 3.1 NATURAL GAS SERVICES

The distribution service shall be offered exclusively by the distributor in its territory, as provided in the *Act Respecting the Régie de l'énergie*. For any customer who is not registered as an emitter, the "cap-and-trade emission allowances system" (CTEAS) service shall be offered exclusively by the distributor in its territory.

Except for customers subject to the receipt rate, the following services may, at the option of the customer, be obtained from the distributor, or subject to Section III of the present document, obtained by the customer itself from one or more suppliers:

- 1. gas supply service, including make-up gas service;
- transportation service;
- 3. load-balancing service.

The distributor shall provide these services by default, in accordance with Section III of the present document, unless the customer notifies the distributor of its intention to provide them itself.

# 3.2 CHOICE OF SERVICES

The conditions relating to a customer's obtaining services from the distributor or providing them itself are specified in Section III of the present document.

# 4. NATURAL GAS SERVICE REQUEST AND CONTRACT

# 4.1 NATURAL GAS SERVICE REQUEST

#### 4.1.1 SERVICE REQUEST PROCEDURE

#### 4.1.1.1 Address Connected to the Distribution System

The service request may be made to the distributor by telephone, mail, e-mail or fax or on the distributor's Internet site. If required by the distributor, the request shall be in writing where the applicant does not intend to occupy the address in question.

A service request by a customer subject to the receipt rate shall be made in writing.

#### 4.1.1.2 Address not Connected to the Distribution System

The service request may be made to the distributor in the manner provided in Article 4.1.1.1 or to one of its representatives duly authorized for this purpose. The list of duly authorized representatives may be obtained from the distributor.

The applicant must be the owner of the property where the service address is located or declare and warrant having, for this purpose, all the authorizations and permissions required from the owner of the property. The applicant shall provide the distributor, upon request, any evidence so attesting.

#### 4.1.2 CONDITIONS FOR ACCEPTANCE OF A SERVICE REQUEST

Acceptance of a service request by the distributor may be subject to:

- 1. payment of a deposit required in accordance with Article 8.1;
- 2. payment, in accordance with Chapter 7, of the amounts owing to the distributor by a customer if the customer continues to occupy the service address covered by the request after the date the natural gas is required.

# 4.1.3 <u>FINANCIAL GUARANTEE FOR THE DISTRIBUTOR'S TRANSPORTATION</u> <u>SERVICE</u>

#### 4.1.3.1 Requirement

At the signing of the contract, and before the distributor reserves the necessary transportation capacity, the distributor may require a financial guarantee in the case of a new application wishing to use the distributor's transportation service whose peak daily projected consumption is of 300 000  $m^3$ /day and over.

Subsequent to the signing of the contract, the distributor may revise the amount of the financial guarantee provided in Article 4.1.3.2 depending on the particular circumstances of each case.

#### 4.1.3.2 Amount

The financial guarantee amount that may be required by the distributor is determined based on the following formula:

Financial Guarantee t (\$) = (Price Tt x Peak Annual Volume x 75%)

Where **Price Tt** = Price of Énergir's **Transportation** Service at year t

**Peak Annual Volume** =  $P \times 365$ 

**P** = Projected Peak Consumption

#### 4.1.3.3 Retention Period

The distribution will retain the financial guarantee until the customer begins its consumption of natural gas.

#### 4.1.3.4 Use of the Financial Guarantee

The distributor may use the financial guarantee to repay development costs incurred to obtain transportation capacity outside the territory.

# 4.2 Information to be Provided for Natural Gas Service Request

#### 4.2.1 INDIVIDUAL

- 1. Mandatory information
  - a) Family name and given name
  - b) Service address covered by the natural gas service request
  - c) Billing address, if different from address covered by the natural gas service request
  - d) Telephone number(s)
  - e) Date for which service is requested
  - f) Date of birth
  - g) Other active accounts with the Distributor
  - h) Last address occupied during the 12 months preceding the request
- 2. Optional information
  - a) Fax number
  - b) E-mail address
  - c) Reading of the metering device

#### 4.2.2 OTHER THAN AN INDIVIDUAL

- 1. Mandatory information
  - a) Name
  - b) Business name
  - c) Service address covered by the natural gas service request
  - d) Billing address, if different from address covered by the natural gas service request
  - e) Telephone number(s)
  - f) Name of contact person
  - g) Date for which service is requested
  - h) Other active accounts with the distributor
  - i) Last address occupied during the 12 months preceding the request
- 2. Optional information
  - a) Fax number
  - b) E-mail address
  - c) Reading of the metering device

# 4.3 **SERVICE CONNECTION**

#### 4.3.1 COST OF WORK AND ECONOMIC INVESTMENT

If the service address is not connected to the distribution system, the distributor shall estimate the cost of the work required and the revenues generated by connection of the service address to the distribution system.

If a connection request is withdrawn, the distributor may bill the applicant if the work has already been undertaken or completed. The amount shall then be based on the actual cost of the work.

A connection request is withdrawn when:

- 1. the applicant notifies the distributor that it withdraws its connection request; or
- 2. the commissioning has not taken place within 12 months of the in-service date agreed upon in the contract, unless the applicant and the distributor enter into an agreement.

#### 4.3.2 CONNECTION CHARGES

If the connection to the natural gas distribution system is requested for a service address to which Rate  $D_1$  will be applicable and for which the projected annual volume will be less than 10,950 m<sup>3</sup>, the connection charge set out in Article 16.1.1 shall be required from the applicant.

If the connection to the gas distribution system is requested by the real estate developer or the builder of the building where the service is required, the applicant shall then deemed to be the owner of the building when the service request is made.

These service connection charges shall be payable in a single payment or, if the applicant is a customer of the distributor, over a period of 24 months or, at the customer's request, in a single payment. If payment of the service connection charges is spread over 24 months and the contract ends before the service connection charges have been fully paid, the balance thereof shall be due immediately.

#### 4.3.3 CHARGES FOR NON-STANDARD SERVICE CONNECTION

The charges for the connection of a service address set out in Article 16.1.2 shall be required from the applicant, when, at its request:

- the connection point is located more than 3 meters from the front corner of the building; or
- the length of the connection pipeline between the property line on which the building is located and the connection point exceeds 50 linear meters.

#### 4.3.4 FINANCIAL CONTRIBUTION FROM THE CUSTOMER

If the revenues generated from connection of the service address to the distribution system do not allow the distributor to earn a return on its investment, based on the estimated cost of the work required, in accordance with the conditions approved by the Régie de l'énergie, the distributor must, on entering into the contract, agree with the customer on a financial contribution payable by the customer except in exceptional cases which will have to be justified *a posteriori* to the Régie. Any service connection charge under Article 4.3.2 shall be additional to this contribution. The distributor may also agree with the customer on a minimum annual obligation.

If a financial contribution is required, it shall be payable in a single payment before the work is started or paid in instalments over the contract term. The distributor shall provide the customer with the details of the financial contribution required.

If a financial contribution is required, the distributor and the customer shall agree before the work is started on matters including:

- 1. the amount of the financial contribution requested from the customer;
- 2. the terms of payment of the financial contribution requested from the customer;

#### Articles 4.3.5 and 4.3.5.1 to 4.3.5.3 added on January 29, 2024.

3. the conditions for repayment, in whole or in part, of the contribution requested from the customer, where applicable.

The distributor may repay, in whole or in part, in accordance with certain profitability conditions set out in writing when the contract is entered into, the financial contribution paid by the customer to make the investment economic.

Notwithstanding the payment of a financial contribution by the customer, the distributor shall remain the exclusive owner of the distribution system.

#### 4.3.5 100% RENEWABLE CONNECTION

#### 4.3.5.1 Distributor Supply Service

For all connection requests involving the installation of a service connection or a metering device following a customer service request, made on or after April 1, 2024, the service address concerned by the connection will be subject to renewable gas supply service.

#### 4.3.5.2 Customer-provided supply service

For all connection requests made on or after April 1, 2024, the natural gas supplied to the distributor for the service address concerned by the connection must be from a renewable source.

#### 4.3.5.3 Exemptions

The following may be exempted from the application of Articles 4.3.5.1 and 4.3.5.2:

- 1. Service requests for a building included in a municipal assessment unit whose predominant use includes industry;
- 2. Service requests for temporary construction heating;
- 3. The supply of natural gas-powered equipment for which there is no similar technological alternative that can be powered by electricity.

# 4.4 LEAD TIMES REQUIRED BY THE DISTRIBUTOR TO PROVIDE NATURAL GAS DISTRIBUTION SERVICE

#### 4.4.1 ADDRESS CONNECTED TO THE DISTRIBUTION SYSTEM

The natural gas shall be made available to the customer immediately if the metering device is not turned off or sealed.

If the metering device is turned off or sealed, the distributor will generally require one to five business days to establish service. However, service may be established later than that if the customer so requests or by reason of constraints relating to the metering device. In the case of metering-device-related constraints, the time required shall be determined for each case and the customer shall be notified of it.

If the service request is made following a service interruption requested by the customer, the distributor shall bill the customer for the service reconnection charge set out in Article 16.1.8.

#### 4.4.2 ADDRESS NOT CONNECTED TO THE DISTRIBUTION SYSTEM

If the service connection requires only a connection pipeline to connect the service address to the existing distribution system, the time between the acceptance of the service request and the natural gas service being made available to the customer shall be:

- 1. 30 business days for the installation of an S6 or S20 metering device;
- 2. 40 business days for the installation of an S40 to S50 or R80 to R450 metering device.

However, service may be established later than that if the customer so requests or by reason of constraints relating to construction. In the case of construction-related constraints, the distributor shall notify the applicant.

If, in addition to the connection pipeline, the service connection requires work on the existing distribution system, the time required by the distributor shall be determined for each case and the applicant shall be notified.

If a request is submitted to the distributor for connection in less time than provided in the first paragraph according to the type of metering device, the charge for the reduction in the service connection time set out in Article 16.1.3 shall be required from the applicant.

# 4.5 FORM, FORMATION AND EFFECTIVE DATE OF CONTRACT

#### 4.5.1 FORM

The contract shall be made in writing in the following cases:

- 1. the customer is billed Distribution Rate D<sub>3</sub>, D<sub>4</sub>, D<sub>5</sub> or D<sub>R</sub>;
- 2. the customer is subject to a minimum annual obligation;
- 3. the customer has entered into a fixed-price agreement;
- 4. the customer has to pay a financial contribution to the distributor;
- 5. the customer who supplies its own natural gas supply service.

#### 4.5.2 FORMATION AND EFFECTIVE DATE

The contract is formed when the distributor informs the new customer that it accepts the natural gas service request or for a written contract, at the moment of the signature. Service shall start on the agreed date.

If a contract with a customer has ended and no contract has been formed with a new customer for the service address, the owner of the property where the service address is located shall be deemed to have entered into a contract if it fails to inform the distributor of its intentions with respect to the natural gas service within 12 business days following delivery by the distributor of written notice to that effect. Then the contract is deemed formed on the date of termination of the former customer's contract.

If a contract with a customer has ended and no contract has been formed with a new customer for the service address and, the owner of the property where the service address is located informs the distributor he wishes to maintain the natural gas service within 12 business days following delivery by the distributor of written notice to that effect, the contract is therefore formed on the date of termination of the former customer's contract.

# 4.6 CONFIRMATION OF ACCEPTANCE OF THE NATURAL GAS SERVICE REQUEST

Following acceptance of the service request, the distributor shall provide to the customer in writing the mandatory information obtained, excluding the list of the customer's other active accounts, with an explanation that the meter reading provided by the customer, if any, may differ from the meter reading used for the billing.

The distributor shall also provide the following information in writing:

- 1. the applicable rate(s);
- 2. the amount and the terms and conditions of the financial contribution, if required;
- information regarding payment methods available to the customer for paying its bill;
- 4. the fact that all customers at the same address are severally liable for full payment of the bills on which they are identified by name;
- 5. the fact that a contract that is not in writing shall remain in effect until resiliated by the customer or, as the case may be, by the distributor;
- 6. the requirement for a deposit, if applicable, and the conditions of repayment thereof.

# 4.7 CONTRACT TERM

If the contract is not in writing, it shall remain in force and effect until resiliated.

If the contract is in writing, its term shall be stated therein.

The distributor may require that the contract term be the same for all the services it provides.

The minimum term of a written contract shall be the term stated in the *Conditions of Service and Tariff* according to the applicable services.

The distributor may require transportation, load balancing and distribution contracts to mature on the same date and that a distribution contract cover the entire period of the other contracted services.

#### 4.8 CONTRACT AMENDMENT

The customer shall be responsible for notifying the distributor of any change to the information provided since the natural gas service request.

The customer may also submit a request for a contract amendment. If the request complies with the *Conditions of Service and Tariff* and if it is economic and operationally possible for the distributor to accept it, the contract may be amended or replaced by a new contract.

If the revenues generated from the contract amendment do not allow the distributor to earn a return on its investment required by the contract amendment, based on the estimated cost of the work required, in accordance with the conditions approved by the Régie de l'énergie, the distributor may, when amending the contract or on entering into the contract, agree with the customer on a financial contribution payable by the customer. If a financial contribution is required, it shall be set in accordance with the terms and conditions provided in Article 4.3.4.

A written contract may not be amended verbally.

In each case provided in this Article, the confirmation referred to in Article 4.6 shall not be sent to the customer.

# 4.9 Contract Termination

#### 4.9.1 WRITTEN CONTRACT

The contract is terminated on the date specified.

Notwithstanding the foregoing, the distributor may resiliate the contract if the customer has interfered with the distributor's pipes, mains, metering device or other device, or used the distributor's natural gas service without its consent.

#### 4.9.2 OTHER CONTRACT

The customer may resiliate the contract by informing the distributor that it ceases or will cease receiving natural gas service. It may do so verbally and shall specify the time after which natural gas service is no longer required.

Where the customer does not inform the distributor that it ceases or will cease receiving natural gas service, the distributor may resiliate the contract at one of the following times:

- 1. when it sees the customer has ceased receiving natural gas service and that no other contract has been entered into for the service address; or
- 2. on the effective date of a new contract with a person requesting natural gas service for the service address in question, except in the case of a customer who owes an amount of money to the distributor and will continue to occupy the service address after the date the gas is required.

Notwithstanding the foregoing, the distributor may resiliate the contract if the customer has interfered with the distributor's pipes, mains, metering device or other device, or used the distributor's natural gas service without its consent.

# 4.10 Force Majeure

When the distributor suffers from a force majeure, it is relieved of its obligation to serve the customer and the customer is relieved of its minimum obligations and, where applicable, of the basic fee under Distribution Rate  $D_1$  for the duration of the force majeure. Under all other circumstances, the customer must assume its minimum obligations, including situations where it suffers from a force majeure.

# 4.11 Changes to Conditions of Service and Tariff

Every contract shall comply with the *Conditions of Service and Tariff*, shall be subject to amendments to this document by the Régie de l'énergie and shall be deemed amended by such amendments.

# 5. MEASUREMENT

# 5.1 METERING DEVICES

#### **5.1.1 METERING DEVICE BELONGING TO THE DISTRIBUTOR**

The distributor shall determine the type of metering device to be used at the metering point or at the receipt point. It shall install, operate and maintain metering device to measure the natural gas withdrawn or injected by the customer.

#### 5.1.2 LOCATION OF AND ACCESS TO THE METERING DEVICE

The distributor shall determine the location of its metering device.

The distributor shall hold, at no cost, all rights of entry, rights-of-way and rights of access to its metering device. The customer shall take the necessary steps to enable the distributor to exercise those rights at the following times:

- 1. At any time for reasons of safety;
- 2. Between 7:00 a.m. and 7:00 p.m. from Monday to Friday except for statutory holidays or at any other time agreed with the customer, for any other reason.

The customer shall not interfere with access to the distributor's metering device.

#### **5.1.3 METERING DEVICE BELONGING TO THE CUSTOMER**

The customer may install, operate and maintain on pipes belonging to it its own metering device at its own expense.

However, the customer's metering device shall be installed downstream from the distributor's metering device in the case of a customer subject to Rate  $D_1$ ,  $D_3$ ,  $D_4$  or  $D_5$  and upstream in the case of a customer subject to Rate  $D_R$ .

Customer's metering device shall be installed, operated and maintained in a manner that does not interfere with the distributor's activities.

# 5.2 MEASUREMENT OF VOLUME OF NATURAL GAS WITHDRAWN OR INJECTED

The metering device shall indicate the volume of natural gas withdrawn or injected by the customer, in either metric or imperial units. For billing purposes, imperial units shall be converted to metric units.

Depending on the type of metering device used, a multiplier factor and a pressure factor may also be applied.

# 5.3 Reading of Metering Device

#### **5.3.1 READING BY THE DISTRIBUTOR**

The distributor shall choose the reading method to be used. The reading of the metering device may be done on site or by a remote device.

However, if the customer requests a reading method other than the one chosen by the distributor, the distributor may bill the customer for the actual costs incurred as a result of using the reading method requested by the customer.

#### **5.3.2 FREQUENCY OF READINGS**

The distributor shall read the metering device with all reasonable diligence using a method consistent with the efficient operation of its business.

The distributor shall read the metering device every two months.

However, in the case of a Rate D<sub>1</sub> customer that withdraws less than 1,000 m<sup>3</sup> a year of natural gas, the distributor shall read the metering device every 12 months.

Furthermore, if the natural gas is billed at Rates  $D_4$ ,  $D_5$ ,  $D_R$  or  $D_3$  and  $D_5$  in combination, the distributor shall read the metering device every day. In the case where natural gas is billed at Rate  $D_3$  without combination with Rate  $D_5$ , the distributor shall read the metering device every month.

#### **5.3.3 READING BY THE CUSTOMER**

When the distributor has not obtained a reading in accordance with Article 5.3.2, it may ask the customer to take the reading and communicate it to the distributor.

In addition, upon arriving at the service address and at the termination of the contract, the customer shall provide to the distributor, at the distributor's request, a reading of the metering device. Otherwise, the distributor shall estimate the volume withdrawn and the distributor may revise that estimate when the distributor obtains a reading of the metering device.

# 5.4 VOLUME OF NATURAL GAS WITHDRAWN OR INJECTED BY THE CUSTOMER

The volume of natural gas withdrawn or injected shall be calculated by determining the difference between two consecutive readings of the metering device. If the distributor does not obtain a reading of the metering device before the bill is issued, the distributor shall estimate the volume of natural gas withdrawn or injected by the customer.

# 5.5 DEFECTIVE METERING DEVICE

If the customer doubts the accuracy of the distributor's metering device, it shall so notify the distributor as soon as possible.

If the distributor determines that there is a defect in the metering device that may have an impact on the billing, it shall so inform the customer as soon as possible.

The customer or the distributor may, at any time, request verification of the metering device in accordance with the *Electricity and Gas Inspection Act*, R.S.C. 1985, c. E-4.

If the customer initiates a request for verification of the metering device, the distributor shall inform the customer of the reasons that lead not to doubt of the metering device accuracy, if any. If the customer maintains its request of verification and that the verification confirms the accuracy of the metering device within the allowed limits, the distributor is then authorized to bill it the fee stipulated in Article 16.1.4.

# 6. BILLING

# **6.1** BILLING METHODS

#### **6.1.1 VOLUME OF NATURAL GAS BILLED**

For billing purposes, the volume will be adjusted to a greater gross heating value of 37.89 MJ/m3.

The distributor shall bill the customer monthly for the actual or estimated volume of natural gas withdrawn or injected at the service address.

However, the distributor may bill every two months a customer billed at Rate  $D_1$  who withdraws less than 1,000 m<sup>3</sup> of natural gas per year.

The billing shall be based on the actual or estimated volume withdrawn or injected at each metering device. However, if the distributor uses more than one metering device at a single metering point or receipt point, the billing shall be based on the sum of the volumes withdrawn or injected at those metering devices as though there were only one.

When a customer, to whom a rate other than  $D_1$  applies, has been billed on the basis of an estimated volume, its bill shall be revised and sent when the actual volume becomes known if the actual volume is less than the estimated volume.

#### **6.1.2 CONTRACTUAL OBLIGATIONS**

If applicable, the distributor shall bill the customer a minimum annual obligation and/or a financial contribution in accordance with Article 4.3.4.

If the customer asks the distributor to turn off and seal the metering device, the basic fee in section III of the present document shall cease to be billed after the turn-off date agreed by the customer and the distributor.

#### **6.1.3 CORRECTION OF ERROR**

If the customer notes an error on its bill, it shall so inform the distributor.

If the distributor notes or is informed of an error on the customer's bill, it shall analyse the bill and notify the customer of the results. If a correction is required, it shall issue a corrected bill. The corrected bill shall replace any other bill issued for the billing period in question.

If the correction results in an amount owing to the distributor by the customer, the customer may spread the payments over a period equal to the re-billed period without any late payment charge or interest as long as it complies with the agreed payment dates.

#### 6.1.4 BILLING PERIOD COVERED BY THE CORRECTION

If the correction results in an amount owing to the distributor by the customer, the period covered by the retroactive correction may not exceed three years from the issue date of the corrected bill arising from the analysis referred to in Article 6.1.3.

However, the retroactive correction shall apply to the entire period affected by the error in the following cases:

1. The distributor was unable to read the metering device because it was unable to exercise its rights of access thereto and was also unable to obtain the reading from the customer in accordance with Article 5.3.3;

- 2. The customer has interfered with the distributor's pipes, mains, metering device or other device, or used the distributor's natural gas without its consent;
- 3. The error is the result of intentional damage to the distributor's metering device;
- 4. The customer was aware of the billing error or the defect in the metering device and failed to inform the distributor thereof;
- 5. The amount of the corrected bill, for the period covered by the retroactive correction is less than the amount of the corrected bill for the three-year period mentioned in the first paragraph.

Notwithstanding the foregoing, if the retroactive correction leads to an amount owing to the distributor by the customer, but the amount of the corrected bill for the three-year period starting on the issue date of the corrected bill results in an amount owing to the customer by the distributor, no corrected bill is issued.

If the retroactive correction results in an amount owing to the customer by the distributor, it shall cover the entire period affected.

# 6.2 BILLS

#### **6.2.1 ISSUE**

Except when a contract ends, the distributor shall issue the bill within a maximum of six business days following:

- 1. the last day of the month; or
- 2. the date the metering device was read.

#### 6.2.2 TRANSMITTAL

The bill shall be sent to the customer the business day after it is issued.

#### 6.2.3 DELIVERY

The distributor shall send the bill to the customer every month or every two months in accordance with Article 6.1.1.

The bill shall be sent by any means selected by the distributor, including by mail, unless the customer asks the distributor to send it electronically.

The customer may ask the distributor to group its bills for delivery. The distributor may bill the customer the actual costs of that service. If it does, the distributor shall notify the customer of the cost of that service before grouping the bills.

#### **6.2.4 INFORMATION APPEARING ON THE BILL**

The bill shall include at least the following items:

- 1. Distributor's telephone number
- 2. Telephone number in case of emergency
- 3. Billing date
- 4. Name of customer
- 5. Account number
- 6. Number of the metering device
- 7. Service address
- 8. Applicable rate

- 9. Period billed
- 10. Consumption, specifying whether actual or estimated
- 11. Total amount
- 12. Amount in arrears and late payment charge
- 13. Due date
- 14. Consumption history available, if applicable
- 15. Minimum annual obligation, if applicable
- 16. Amount and date of last payment
- 17. Amount of financial contribution requested from customer to make the investment economic, if applicable
- 18. Amount of deposit and interest paid, if applicable
- 19. Rate adjustment arising from any commercial program approved by the Régie de l'énergie, if applicable

# 7. PAYMENT

# 7.1 DUE DATE

There shall be at least 12 business days between the date the bill is sent and the due date shown thereon. However, if bills are grouped as provided in Article 6.2.3, the time elapsed may be less than 12 business days because each bill shall retain its own due date shown thereon.

The customer shall pay the total amount billed that appears on the bill no later than the due date shown thereon.

The customer may contact the distributor at any time to propose a payment agreement as provided in Article 9.1.

#### 7.2 TERMS

#### 7.2.1 PAYMENT METHODS

The customer shall pay its bill in Canadian dollars in one of the following ways:

- 1. Through a financial institution, by means including automatic withdrawal or by Internet;
- 2. By mail (for cheques and money orders);

A customer who wishes to use a credit card to pay its bill may do so through a third party accepting that method of payment, which will pay the distributor in accordance with one of the payment methods mentioned in identation 1 and 2 of the first paragraph, to the extent that no fees are charged to the distributor.

Regardless of the method of payment selected, the payment date shall be the date the distributor receives the payment from the customer or third party, if applicable.

The distributor shall bill the customer the charge provided in Article 16.1.5 for each payment not honoured by a financial institution, except in the case of an error for which the distributor is responsible.

#### 7.2.2 COMPENSATION PROHIBITION

The customer may not, without the distributor's written consent, deduct from its payment an amount owed to the customer by the distributor or a customer claim against the distributor.

#### 7.2.3 EQUAL PAYMENTS PLAN

The customer whose natural gas service is billed under Rate  $D_1$  and who, when it so requests, does not have an unpaid balance at the due date, may avail itself, at any time and at no additional cost, of the equal payments plan.

The distributor shall determine the amount of the monthly instalments when the customer opts for the equal payments plan. The amount shall be based on the consumption history at the service address, the average temperature for the last five years, the price of natural gas service and the number of monthly instalments between the time the customer opts for the plan and the June or July renewal date.

The monthly instalment shall be revised at least once a year, on the June or July renewal date.

When the equal payments plan is renewed in June or July, any debit balance in excess of the monthly instalment shall be spread over the next 12 months and any credit balance that is equal to or less than the new monthly instalment shall be applied to the customer's next bill. A credit balance that exceeds the new monthly instalment shall be refunded by cheque or by deposit to the customer's bank account.

The distributor shall inform the customer in writing of the amount of the monthly instalment when it is established or revised, as applicable.

A customer who no longer wishes to avail itself of the equal payments plan shall so inform the distributor and may do so at any time without prior notice. Termination of the equal payments plan shall take effect on the customer's next bill.

The distributor may terminate the equal payments plan if the unpaid balance at the due date is equal to or greater than two monthly payments. The customer shall be informed of the termination of the equal payments plan by means of the bill.

#### 7.3 LIABILITY

#### 7.3.1 WRITTEN CONTRACT

All customers who have entered into a given contract shall be solidarily liable for full payment of the bills.

#### 7.3.2 OTHER CONTRACT

All customers at the same service address shall be solidarily liable for full payment of the natural gas bills on which they are identified by name.

# 8. DEPOSIT

# 8.1 REQUIREMENT

If the distributor requires a deposit for one or more natural gas services at a service address, it shall inform the customer of the reasons for it.

The customer may satisfy the deposit requirement by paying a cash amount or by providing equivalent security in order to guarantee payment for natural gas services.

If the deposit is paid in cash and the customer is an individual, the individual shall provide its social insurance number. The distributor may use the social insurance number for tax purposes only.

#### 8.1.1 DOMESTIC USE

#### 8.1.1.1 Natural Gas Service Request

When service is requested, the distributor may require a deposit in the following cases:

- The applicant fails to provide the following mandatory information in accordance with Article 4.2.1: family name and given name, date of birth and last address occupied in the 12 months preceding the request;
- 2. The applicant has in the past interfered with the distributor's pipes, mains, metering device or other device, has used the distributor's natural gas without its consent or has made a fraudulent payment.

#### 8.1.1.2 During the Term of the Contract

The distributor may require a deposit in the following cases:

- 1. The customer's natural gas service has been interrupted by the distributor for non-payment of a bill on the due date;
  - However, the distributor shall not require a deposit from a customer using natural gas for space heating if the service interruption for non-payment and the reconnection both occur between December 1 and March 1 of the following year;
- 2. The customer has in the past interfered with the distributor's pipes, mains, metering device or other device, has used the distributor's natural gas without its consent or has made a fraudulent payment.

#### 8.1.2 OTHER USES AND CUSTOMERS SUBJECT TO RATE $D_R$

#### 8.1.2.1 Natural Gas Service Request

When service is requested, the distributor may require a deposit in the following cases:

- 1. Following a credit check of the applicant, if the distributor considers it necessary;
- 2. The applicant has in the past interfered with the distributor's pipes, mains, metering device or other device, has used the distributor's natural gas without its consent or has made a fraudulent payment.

#### 8.1.2.2 During the Term of the Contract

The distributor may require a deposit in the following cases:

- 1. The customer has failed to pay a natural gas bill on the due date during the previous 12 months;
- The customer has in the past interfered with the distributor's pipes, mains, metering device or other device, has used the distributor's natural gas without its consent or has made a fraudulent payment;

- 3. At some point during the previous 24 months, the customer has availed itself of or was under the protection of the provisions of the *Bankruptcy and Insolvency Act*, R.S.C. 1985, c. B-3, the *Companies' Creditors Arrangement Act*, R.S.C. 1985, c. C-36, or the *Farm Debt Mediation Act*, S.C. 1997, c. 21;
- 4. The customer wishes to avail itself of the distributor's supply service;
- 5. Following a credit assessment of the customer, when the customer makes a request of modification to its facilities with the effect that its consumption is increased to the equivalent of the double of the last 12 months;
- 6. Following a credit assessment of a new customer, following an assignment of contract.

### 8.2 AMOUNT

The amount of the deposit required by the distributor shall be based on estimated or historical volumes withdrawn at the service address during a 12-month period or on the maximum contract capacity in the case of a customer subject to Rate  $D_R$ .

#### **8.2.1 DOMESTIC USE**

If the customer's service is interrupted for non-payment, in accordance with Article 9.4.3, for the first time in 12 months, the amount of the deposit shall not exceed the amount of the highest bill during a 12-month period.

In any other situation, the amount of the deposit shall not exceed the sum of the amounts of the highest two consecutive bills during a 12-month period.

#### 8.2.2 OTHER USES

The amount of the deposit, taking into consideration all services offered by the distributor, shall not exceed the sum of the amounts of the highest two consecutive, historical or estimated, bills during a 12-month period.

#### 8.2.3 CUSTOMERS SUBJECT TO RATE D<sub>R</sub>

The amount of the deposit required by the distributor shall not exceed the amount equivalent to the minimum daily obligation for a 12-month period.

#### 8.3 PAYMENT

The cash deposit shall be paid to the distributor in accordance with the payment methods specified in Article 7.2.1. The remittance of any other security shall be made in accordance with the terms and conditions thereof. The distributor shall confirm in writing the payment of the deposit.

If the metering device is turned off and sealed, the distributor may require the deposit to be paid before the metering device is unsealed and turned on by the distributor.

If the metering device is not turned off or sealed, the deposit shall be paid within the time indicated by the distributor, in accordance with Article 7.1.

The distributor shall transfer any cash deposit to a trust account.

The customer may contact the distributor at any time to propose a payment agreement as provided in Article 9.1.

# **8.4** RETENTION PERIOD

A deposit may be initially retained for:

- 12 consecutive months or as long as the mandatory information set out in Article 4.2.1 has not been provided, in the case of a customer who uses natural gas for domestic use;
- 2. 36 consecutive months in the case of a customer who uses natural gas for any other use;
- 3. 60 consecutive months in the case of a customer subject to rate D<sub>R</sub>.

During the deposit retention period, if a final notice is sent to the customer, the distributor shall renew the deposit retention period for a period of 12 months if the new expiry date is later than the original expiry date of the retention period.

If, for a period of 12 consecutive months, the customer who uses natural gas for another use pays all of its bills by the due date specified therein, the deposit is returned in full, as provided in Article 8.6.2.

#### 8.5 Interest on Cash Deposit

#### **8.5.1 INTEREST RATE**

The deposit shall produce interest that belongs to the customer.

The annual interest rate on the deposit shall be established on January 1 of each year based on the rate of non-registered and non-redeemable Guaranteed Investment Certificates (GICs) for a 12-month term offered to individuals, as published by the National Bank of Canada on the first bank business day of each year.

The distributor shall submit to the Régie de l'énergie, no later than January 30 of each year, a report showing the rate of the source of the information used to establish it.

#### **8.5.2 PAYMENT OF INTEREST**

During the deposit retention period, the distributor shall credit the interest produced by the deposit on the first bill issued at the beginning of each calendar year.

# **8.6** Use or Return to the Customer

#### 8.6.1 <u>USE OF THE DEPOSIT</u>

#### 8.6.1.1 During the Term of the Contract

During a contract term and notwithstanding a customer's request to that effect, the distributor may not apply the deposit to a natural gas bill.

However, in the case of a service interruption for non-payment, as provided in Article 9.4.3, if the bill issued following the interruption for non-payment is unpaid on the due date, the distributor may, without prejudicing its other rights and recourses, apply the cash deposit or the proceeds from the realization of any other security provided by the customer to a bill unpaid by its due date.

#### 8.6.1.2 On Termination of the Contract

If a contract is terminated as provided in Article 4.9, the distributor may, without prejudicing its other rights and recourses, apply the cash deposit or the proceeds from the realization of any other security provided by the customer to a bill unpaid by its due date.

After application to the unpaid bill, any balance from the cash deposit or other security shall be returned to the customer.

#### 8.6.1.3 Customers Subject to Rate D<sub>R</sub>

The distributor may, without prejudicing its other rights and recourses, apply in part the cash deposit or the proceeds from the realization of any other security provided by the customer to a bill unpaid by its due date. The proportion of the deposit thus applied shall be determined by the distributor. However, the residual amount of the deposit may not be less than the equivalent of the largest two consecutive bills of a 12-month period.

#### 8.6.2 RETURN OF THE DEPOSIT

No more than 30 days after the deposit retention period has expired or the mandatory information set out in Article 8.1.1.1 has been complied with, the distributor shall refund to the customer by cheque or by deposit to the customer's bank account its total cash deposit with interest not yet credited or return the security it holds to the customer. If the amount to be refunded is lower than \$5.00, the distributor will, at the customer's request, refund it by cheque or by deposit to the customer's bank account.

However, when a contract expires, the period for returning the deposit may be extended up to 10 business days to ensure payment is honoured.

# 9. COLLECTION

# 9.1 PAYMENT AGREEMENT

The customer may contact the distributor at any time to propose a payment agreement to spread the payment of the unpaid amounts owing on the due date over a period of time and to provide for full payment of the bills issued during the period covered by the agreement.

The distributor shall inform the customer of this possibility on any collection notice sent to it.

# 9.2 PAYMENT DEFAULT

The customer shall immediately pay in full any unpaid amount on the due date.

# 9.3 LATE PAYMENT CHARGE

The late payment charge for which the rate is set out in Article 16.1.6 shall be added each month to the unpaid balance from the day following the due date.

#### 9.4 Collection Procedures

With the exception of the cases specifically covered by the *Act respecting the mode of payment for electric and gas service in certain buildings*, R.S.Q., c. M-37, the collection procedures for non-payment on the due date shall be as follows.

#### 9.4.1 COLLECTION NOTICES

#### 1. Reminder

If a bill remains unpaid after the due date, the distributor shall send a written reminder to the billing address or communicate a reminder by telephone.

#### 2. Final notice

If a bill remains unpaid following the reminder, the distributor shall send a final written notice under separate cover to the billing address using a method that provides proof the notice was sent. The notice shall inform the customer that unless payment is made, natural gas service may be interrupted.

Before interrupting service for non-payment between December 1 and March 1 of the following year, the distributor shall contact a domestic-use customer who uses the natural gas for space heating to propose a payment agreement.

#### 9.4.2 COLLECTION VISIT

If the bill is not fully paid following the final notice and there is no payment agreement or a payment agreement has not been complied with, the distributor may visit the service address to collect the amounts due on the date of that visit. Article 9.4.2 does not apply to customers subject to Rate  $D_R$ .

The distributor may make such a collection visit from 8:00 a.m. to 8:00 p.m., from Monday to Saturday.

Between December 1 and March 1 of the following year, the distributor may make a collection visit to the service address of a domestic-use customer who uses the natural gas for space heating, to propose a payment agreement.

Following a collection visit, the collection charge provided in Article 16.1.7 shall be billed to the customer who pays its bill before service is interrupted.

#### 9.4.3 INTERRUPTION FOR NON-PAYMENT

At the time of the collection visit, or in the case of customers subject to Rate  $D_R$ , after the sending of a final notice pursuant to Article 9.4.1, if the amount required in the final notice or agreed to under a payment agreement remains unpaid, the distributor may interrupt natural gas service. In that event, the distributor shall ask the customer to notify the owner of the property affected by the interruption, if applicable.

However, between December 1 and March 1 of the following year, the distributor may interrupt the natural gas service of a domestic-use customer who uses natural gas for space heating only in the following cases:

- 1. The customer and the distributor have not entered into a payment agreement; or
- 2. The customer is not complying with the payment agreement entered into with the distributor.

#### 9.5 RECONNECTION

Following a service interruption for non-payment, the distributor shall reconnect the service when the customer pays the amounts due and the reconnection charge set out in Article 16.1.8 and provides any deposit required.

In the event that a new contract comes into effect with a person requesting service for a service address affected by the interruption for non-payment, the reconnection charge pursuant to Section 16.1.8 may be billed to the customer causing the interruption for non-payment notwithstanding the end of the distribution contract to which he was a party.

# **SECTION III - TARIFF**

### 10. OPTIONS AVAILABLE TO CUSTOMERS

### **10.1** Service Options

Subject to Article 17.2.2, a customer's choice of services, as provided in Chapter 3, is subject to certain advance notices. Under certain conditions, it may be possible for the distributor to accept the customer's request on shorter notice; however, the rate impact of such request on all customers could justify refusal of the request.

A customer who uses the distributor's natural gas supply service must, for the equivalent volumes, use all of the distributor's services except for the "cap-and-trade emission allowances system" service for which the withdrawals of a customer can be partially or totally exempted.

A customer who provides its own transportation service must, for the equivalent volumes, at the same time provide the natural gas it withdraws at its facilities.

A customer who uses the distributor's natural gas supply service shall be subject, by default, to the variable price of natural gas supply not determined by a fixed-price supply agreement.

# 10.2 COMBINATION OF CUSTOMER'S AND DISTRIBUTOR'S SERVICES

A customer may not, at a single metering point, for either natural gas supply and transportation service, including make-up gas service, simultaneously use the distributor's services and provide its own services.

In addition, a customer who wishes to supply the distributor with the natural gas it withdraws at its facilities may not combine supply service with transfer of ownership and supply service without transfer of ownership.

Exceptionally, however, a customer who uses firm service as well as interruptible service at a single metering point shall be entitled to use its own transportation service for the firm portion of its load while using the distributor's transportation service for the interruptible portion. In addition, a customer using "Make-up Gas Service to Avoid an Interruption" may combine its own natural gas supply and transportation services with those of the distributor for this make-up portion of its load.

Also, a customer who provides, in part, gas from renewable sources at a single metering point shall be entitled to:

- 1. use the distributors' supply service as well as its own supply service: when this gas from renewable sources is produced within the franchise, a customer shall be entitled, furthermore, at a single metering point, to use the distributor's transportation service as well as, for the gas from renewable sources produced within the franchise, its own transportation service.
  - The natural gas then provided by a customer must be "with transfer of ownership";
- 2. use the gas from renewable sources supply tariff for the distributor's supply service as well as supply its own service of traditional natural gas. The volume of traditional natural gas supplied by the customer during each contractual period must correspond to the total volume of supply that he intends to withdraw during the same period.
  - For direct purchase supply customers without transfer of ownership, during each contract period, Énergir will apply to the customer's monthly bill a credit equivalent to the price of network gas for that month multiplied by the volume consumed in gas from renewable sources by the customer.

### 10.3 COMBINATIONS OF SERVICES

A customer who uses the distributor's natural gas supply service must, for the equivalent volumes, at the same time use the distributor's transportation and load-balancing services.

A customer who wishes to use the "Competitive Make-up Gas" service must use the transportation supplied from time to time by the distributor.

A customer who provides the transportation service needed to move the natural gas it withdraws at its facilities to the distributor's territory must, for the equivalent volumes, at the same time supply the distributor with the natural gas it withdraws at its facilities.

### **10.4 CUSTOMER GROUPING**

Customers may form a group to provide their natural gas supply service. Subject to Article 17.2.1, customers may form a group to provide their transportation and load-balancing services if they are all related persons, each to all the others, within the meaning of the *Taxation Act*, R.S.Q., c. I-3. In the latter case, the customer grouping shall also apply to natural gas supply service.

For all customer groupings, only the monitoring of volume imbalances shall be carried out for all of the grouped metering points as if there were a single metering point. Billing for all of the distributor's services, including billing of volume imbalances, will continue to be made on an individual basis in accordance with each service's rate provisions.

In the case of customers whose service address is covered by Article 4.3.5, only groupings with other customers whose service address is covered by Article 4.3.5 will be possible.

Customer groupings are not permitted for distribution service.

### 11.1 DISTRIBUTOR'S SERVICE

### 11.1.1 APPLICATION

For any customer who wishes to purchase from the distributor the natural gas it withdraws at its facilities.

A customer whose normalized annual load is between 7,500 m<sup>3</sup> and 1,168,000 m<sup>3</sup> may enter into a fixed-price supply agreement with the distributor.

### 11.1.2 NATURAL GAS SUPPLY RATE

### 11.1.2.1 Natural Gas Supply Price

For each m<sup>3</sup> of volume withdrawn, the traditional natural gas supply price, as of December 1, 2023, is 12.087¢/m<sup>3</sup>. The price may be adjusted monthly to reflect actual cost of acquisition.

For each  $m^3$  of volume withdrawn, the gas from renewable sources supply price, as of December 1, 2023, is  $72.457 \text{¢/m}^3$ .

When a customer enters into a fixed-price supply agreement with the distributor, in writing, within the allowed timeframe, the specific gas supply price shall be the cost of acquisition of the natural gas from the specific supplier in accordance with the customer's commitment under the agreement. The distributor does not guarantee the fixed gas supply price agreed upon with the specific supplier. The customer is billed this specific price commencing on the day deliveries from the specific supplier begin and for as long as these deliveries continue. Should the specific supplier no longer be able to meet its commitments to the distributor, the customer will be transferred to the distributor's variable-price natural gas supply service once the natural gas already delivered by the specific supplier for the customer in question has been fully used.

### 11.1.3 TERMS AND CONDITIONS

### 11.1.3.1 Daily Contract Volume (DCV)

For a customer who has entered into a fixed-price supply agreement with the distributor, the DCV is the volume the specific supplier agrees to deliver to the distributor over the course of one day at an agreed upon delivery point. The DCV is agreed on the basis of the estimated average daily volume for the contract period.

For purposes of load balancing of customers grouped by the specific supplier, the individual DCVs shall be those provided by the specific supplier, failing which they shall be prorated according to the estimated volumes for the contract period.

### 11.1.3.2 Prior Notice of Entry

A customer who wishes to avail itself of the distributor's traditional natural gas supply service must so notify the distributor in writing at least 60 days in advance.

On shorter notice, the customer may avail itself of the distributor's traditional natural gas supply service only if it is operationally possible for the distributor to provide it.

### 11.1.3.3 Prior Notice of Withdrawal

Subject to Article 11.1.3.6, a customer who wishes to opt out of the distributor's traditional natural gas supply service must so notify the distributor in writing at least 60 days in advance.

Notwithstanding the foregoing, the customer must have used the distributor's traditional natural gas supply service for a minimum of 12 months prior to retiring from the service.

### Modifications to Article 11.1.3.5, January 29, 2024.

### 11.1.3.4 Prior Notice of Commitment to a Fixed-Price Supply Agreement

A customer who wishes to enter into a fixed-price supply agreement with the distributor must so notify the distributor in writing at least 60 days, but no more than 120 days, in advance.

In addition, a customer who is currently using the distributor's natural gas supply service may enter into a fixed-price supply agreement with the distributor provided the customer has used the distributor's natural gas supply service:

- 1. for a minimum of 12 months;
- 2. for a minimum 12 months in addition to the number of months remaining under the fixed-price supply agreement when it is cancelled if the customer uses the distributor's natural gas supply service after terminating its fixed-price supply agreement before the end of the agreed term.

On shorter notice, the customer would be entitled to enter into a fixed-price supply agreement with the distributor only if the distributor agrees to it.

### 11.1.3.5 Gas from Renewable Sources

Terms and conditions for subscribing and modifying the consumption of the supply service

A customer who wishes to make or modify the portion of its consumption subject to the gas from renewable sources supply rate must submit a request in writing to the distributor at least 60 days in advance, indicating the targeted consumption percentage. Inside the notice period requested, the customer may consume the quantity of gas from renewable sources requested only if it is possible for the distributor to accept it.

A customer who wishes to subscribe to the gas from renewable sources supply rate may commit to consuming gas from renewable sources for a predetermined quantity and duration of a minimum of 12 months by waiving the possibility of terminating its subscription with a 60 days notice.

The terms of this article do not apply to service addresses covered by Article 4.3.5.

## 11.1.3.5.1 Volumes Acquired in Excess of the Percentage of Gas from Renewable Sources by the Regulation respecting the quantity of gas from renewable sources to be delivered by a distributor

In the event that volumes of gas from renewable sources must be acquired in excess of the percentage of gas from renewable sources prescribed by the *Regulation respecting the quantity of gas from renewable sources to be delivered by a distributor* in order to specifically meet the demand of a customer wishing to subscribe to the gas from renewable sources supply rate, the distributor shall require that a contract be concluded with the customer, including a minimum annual obligation as defined in Article 11.1.3.7, if the customer's demand for gas from renewable sources is more than 1 Mm³ or if the acquisition of the specific volume for the customer has an impact of more than 1% on the gas from renewable sources supply rate in effect.

### 11.1.3.5.2 List of Demand and Attribution of New Units

Despite the foregoing at the present Article 11.1.3.5, any new qualification or increase of consumption percentage subject to the gas from renewable sources rate will be given only if it is operationally possible for the distributor to supply the gas from renewable sources to the customer. If it is not operationally possible to provide gas from renewable sources to a customer, the customer will be registered to the request list on a first-come, first on the list basis. Thereafter, the allocation of new available gas from renewable sources units will be made according to the following terms and conditions:

- For the customers whose service address is associated with a single-family home, duplex our triplex, 50,000 m<sup>3</sup> will be allocated, according to the ranks on the lists;
- For the other customers, the units will be allocated according to the ranks on the list:
  - o During the first round, in maximum tiers of 50,000 m<sup>3</sup>;
  - o During the second round, up to a percentage of consumption targeted by the customer.

#### 11.1.3.5.3 Terms of the Financial Settlement

In the event the distributor is unable to supply the percentage of gas from renewable sources targeted by the customer, the distributor may transfer part of the customer's consumption at the traditional natural gas supply rate and settle the price difference through a financial settlement.

The financial settlement doesn't apply to customers whose natural gas consumption is 100% gas from renewable sources or who have committed to the distributor to consume gas from renewable sources for a predetermined quantity and duration, except in the case where the volumes of gas from renewable sources sold to these customers exceed the volumes of gas from renewable sources available for sale. The calculation of the financial settlement is made at the end of the rate year. The average supply and CTEAS prices for the period October 1 to September 30 are used to determine the financial settlement amount.

The financial settlement is calculated as follows:

Financial settlement volumes \* (Average price of traditional natural gas supply + Average price of CTEAS – Average price of gas supply from renewable sources)

where:

Volumes financial settlement =

Quantity of gas from renewable sources charged to the customer

(Quantity of gas from renewable sources charged to the customers subject to financial settlement \* Quantity of gas from renewable sources charged in excess of available inventories)

### 11.1.3.5.4 Prior Notice of Withdrawal

A customer who wishes to withdraw from the distributor's gas from renewable sources supply rate must notify the distributor in writing at least 60 days in advance. However, a customer under contract with the distributor for a predetermined quantity and duration may not withdraw from the gas from renewable sources supply rate or reduce the portion of its consumption subject to that rate before the end of its contract.

The terms of this article do not apply to service addresses covered by Article 4.3.5.

### 11.1.3.6 Contract Term

Any written traditional natural gas supply service contract must be for a minimum of 12 months.

### 11.1.3.7 Minimum Annual Obligation

The volume of gas from renewable sources withdrawn in each contract year must be at least equal to the applicable MAO for the same period.

### 11.1.3.7.1 Establishment of MAO

The MAO is equal to the quantity of gas from renewable sources predetermined annually, as defined in the engagement with the distributor, multiplied by 75%.

### 11.1.3.7.2 Volume Deficiency Billing

If, at the end of a contract year, the customer has withdrawn a volume that is less than its MAO, the customer will be billed for the deficiency volume at the price in the second paragraph of Article 11.1.2.1 less the price in the first paragraph of Article 11.1.2.1 and the price in Article 15.1.2.1.

### 11.1.3.8 Natural Gas Quality

The monthly average gross heating value of the natural gas delivered shall be at least 36.00 MJ/m³ unless the customer and the distributor agree on a lower value.

### 11.2 CUSTOMER-PROVIDED SERVICE

### 11.2.1 APPLICATION

For any customer who wishes to supply the distributor with the natural gas it withdraws at its facilities.

### 11.2.2 RATE

### 11.2.2.1 Service Price

With transfer of ownership: The distributor purchases the natural gas from the customer at the distributor's natural gas supply price at the time of delivery at an agreed delivery point and resells the natural gas to the customer at its facilities at the natural gas supply price in effect at the time.

<u>Without transfer of ownership</u>: The distributor receives the natural gas from the customer at an agreed upon delivery point and delivers it to the customer at its facilities. The customer shall not be billed for the price of the distributor's natural gas supply service.

### 11.2.3 TERMS AND CONDITIONS

### 11.2.3.1 Daily Contract Volume (DCV)

The DCV is the volume the customer agrees to deliver to the distributor over the course of one day at an agreed upon delivery point. The DCV is agreed on the basis of the estimated average daily volume for the contract period.

For purposes of individual billings of grouped customers' volume imbalances and load balancing, the individual DCVs shall be those provided by the grouped customers, failing which they shall be prorated according to the estimated volumes for the contract period.

### 11.2.3.2 Adjustment of Daily Contract Volumes (DCVs)

### 11.2.3.2.1 Prior Notice

DCVs may be adjusted only when it is economic and operationally possible for the distributor to agree to the adjustment.

A customer must address its request for a DCV adjustment to the distributor as soon as possible and no later than 10:00 a.m. (ET) on the day preceding the day on which the adjustment would take effect. On shorter notice, the DCVs can be adjusted only if the distributor agrees to it.

### 11.2.3.2.2 Conditional Adjustment

Before accepting a DCV adjustment request, the distributor may require that the customer agree to adjust its load proportionally. In the absence of a proportional load adjustment, the customer's DCV shall be considered non-adjusted and the customer's bill shall be based on this non-adjusted DCV.

### 11.2.3.2.3 Anticipated Contract-Period Volume Imbalance

If the distributor anticipates that the customer will have a volume imbalance of more than 5% at the end of the contract period, it may require the customer to adjust its DCV or load in order to avoid such imbalance.

### 11.2.3.3 Volume Imbalances

### 11.2.3.3.1 Daily Volume Imbalances

A daily volume imbalance occurs when the customer delivers, over the course of one day, a volume of natural gas different from what it has agreed to deliver (DCV). When the volume delivered exceeds the DCV, there is a delivery overage; when the volume delivered is less than the DCV, there is a delivery shortage.

### Modifications to Article 11.2.3.3.1, January 29, 2024.

The delivery overage is purchased by the distributor, and the delivery shortage is sold to the customer, at the following price:

- 1. from 0% to 2% of the initial DCV:
  - a) the distributor's natural gas supply price plus, as applicable, the distributor's transportation price;
- 2. above 2% of the initial DCV:
  - a) the lower, in the case of an overage, or the higher, in the case of a shortage, of:
    - the distributor's natural gas supply price, and
    - the market price for the same service at the time the imbalance occurred;
  - b) this price shall be increased, as applicable, by the lower, in the case of an overage, or the higher, in the case of a shortage, of:
    - the distributor's natural gas supply price, and
    - the market price for the same service at the time the imbalance occurred;
  - c) in addition, the distributor shall bill the customer for all additional costs incurred to manage the delivery overage or shortage.

Notwithstanding the existence of a daily volume imbalance, the volume the customer has agreed to deliver, the initial DCV, shall continue to be used, as applicable, to calculate the contract-period volume imbalance and to bill the load-balancing service.

In the case of a customer who supplies the distributor with the natural gas it withdraws at its facilities, with or without transfer of ownership, the delivery overage under a "Make-up Gas to Avoid an Interruption" contract is transferred to the regular supply contract. The transportation service related to this delivery overage is purchased by the distributor on the terms and conditions described above.

Exceptionally, when a customer uses at a single metering point both the distributor's traditional natural gas services and gas from renewable sources produced within the franchise, or when a customer uses only gas from renewable sources produced within the franchise, the delivery overage is purchased by the distributor and the delivery shortage is sold to the customer, at the distributor's traditional natural gas supply price.

This section does not apply to a customer whose service address is covered by Article 4.3.5.

### 11.2.3.3.2 Contract-Period Volume Imbalances

A contract-period volume imbalance occurs when the customer withdraws, during the contract period, a volume of natural gas different from what it has agreed to deliver (sum of the DCVs).

When a customer uses at a single metering point both the distributor's natural gas services and gas from renewable sources, the volume withdrawn considered in the parameter calculations of the contract-period volume imbalances is the gas from renewable sources volume in the customer's supply contract.

A customer who is not subject to a "Competitive Make-up Gas" contract can choose one of the following two options:

- 1. Financial settlement of the volume imbalance at the end of the contract period; or
- 2. Carry-forward, over the 12 months of the following contract period, of a volume imbalance of up to 5% of the volume withdrawn during the contract period; any excess over 5% of the volume withdrawn must still be settled financially.

The choice must be made by written notice to the distributor before the start of the supply contract. If written notice is not provided, any volume imbalance will be settled financially at the end of the contract period.

Notwithstanding a customer choice to carry forward, the distributor may require financial settlement of the volume imbalance at the end of the contract period if the customer represents a financial risk.

A customer subject to a "Competitive Make-up Gas" contract must settle financially the volume imbalance for the contract period.

### Modifications to Article 11.2.3.3.2, January 29, 2024.

When the volume withdrawn is less than the sum of the DCVs, there is a delivery overage; when the volume withdrawn exceeds the sum of the DCVs, there is a delivery shortage.

The delivery overage is purchased by the distributor, and the delivery shortage is sold to the customer, at the following price:

- 1. from 0% to 5% of the volume withdrawn:
  - a) if the customer chose the financial settlement option:
    - the distributor's average price for the supply of gas from a renewable source during the contract period plus, where applicable, the average transportation price for the contract period for customers whose service address is covered by Article 4.3.5.;
    - the distributor's average traditional natural gas supply price during the contract period plus, as applicable, the average transportation price during the contract period for all other customers;
  - b) if the customer chose to carry forward the volume imbalance:
    - no purchase or sale, as this portion is transferred to the following contract period;
- 2. above 5% of the volume withdrawn:
  - For customers whose service address is covered by article 4.3.5:
  - a) the lesser of, in the case of a surplus:
    - the distributor's average conventional natural gas supply price during the contract period, and
    - the average market price of the same service during the contract period;
  - b) the distributor's average price for the supply of gas from renewable sources during the contract period in the case of a shortfall;
  - c) in addition, the distributor will bill the customer for any additional costs incurred to manage the delivery overage or shortage.
  - ii. For all other customers:
  - a) the lower, in the case of an overage, or the higher, in the case of a shortage, of:
    - the distributor's average traditional natural gas supply price during the contract period, and
    - the average market price for the same service during the customer's contract period;
  - b) this price shall be increased, as applicable, by the lower, in the case of an overage, or by the higher, in the case of a shortage, of:
    - the distributor's average transportation price during the contract period, and
    - the average market price for the same services during the customer's contract period;
  - c) in addition, the distributor shall bill the customer for all additional costs incurred to manage the delivery overage or shortage.

Exceptionally, when a customer uses at a single metering point both the distributor's natural gas services and gas from renewable sources produced within the franchise, or when a customer uses only gas from renewable sources produced within the franchise, the delivery overage or the delivery shortage shall be exempted from the contract-period volume imbalances rules in this Article.

### 11.2.3.3.3 Residual Billing of Certain Imbalances

In the case of a delivery overage, a customer providing its own natural gas supply service with transfer of ownership, whose natural gas delivery overage has already been purchased by the distributor at the distributor's natural gas supply price, shall be billed only the difference between the price already paid by the distributor and the price resulting from the application of Articles 11.2.3.3.1 and 11.2.3.3.2.

In the case of a delivery shortage, a customer providing its own natural gas supply service with transfer of ownership, and, as applicable, using the distributor's transportation service, whose natural gas delivery shortage has already been billed by the distributor at the natural gas supply price and, as applicable, at the distributor's transportation price, shall be billed only the difference between the price already charged by the distributor and the price resulting from the application of Articles 11.2.3.3.1 and 11.2.3.3.2.

### 11.2.3.3.4 Billing of Volume Imbalances in the Case of Customer Groupings

The daily or contract period volume imbalance of grouped customers, as applicable, is prorated according to their respective volumes withdrawn during the contract period. The volume imbalance is then billed individually to the customers in accordance with the provisions of Articles 11.2.3.3.1, 11.2.3.3.2 and 11.2.3.3.3.

The volume imbalance may be billed to a single member of a customer grouping if requested in writing by the same member.

### 11.2.3.3.5 Exchange of Volume Imbalances among Customers

Customers may exchange their volume imbalances among themselves provided they notify the distributor before the latter has billed them.

### 11.2.3.3.6 Compensation

In the event a customer defaults on payment of any amount related to natural gas supply, the distributor has the right to offset it against any amount the distributor owes the customer.

### 11.2.3.4 Prior Notice of Entry

Subject to Article 11.1.3.5, a customer who wishes to supply the distributor with the natural gas it withdraws at its facilities must notify the distributor in writing at least 60 days in advance.

Notwithstanding the foregoing, the customer must have used the distributor's supply service for a minimum of 12 months prior to retiring from the service.

### 11.2.3.5 Customer Obligations

A customer must:

- 1. be the actual owner and end-user of the natural gas;
- ensure the security of its supply. In particular, in the event that a supplier cease its deliveries, the
  customer shall, within a period not exceeding the last day of the month following the knowledge of the
  facts, identify a new supplier. The customer will be transferred to the distributor's natural gas supply
  service upon failure to provide the identification within the prescribed period and will be subject to
  Article 11.1.3.5;
- provide to the distributor all information related to the volume it intends to withdraw at its facilities, by distinguishing the volumes of gas from renewable sources from the volumes of traditional natural gas, in order to allow the distributor to adequately plan, manage and control all volumes carried in its distribution system;
- 4. agree that the natural gas it withdraws will be a mixture of the natural gas it sold or delivered to the distributor with any other natural gas the distributor may carry in its distribution system;
- 5. hold the required authorizations or ensure that they are held, if necessary, for export, outside the province of origin, of the natural gas it intends to sell to the distributor or have delivered to its facilities;
- 6. ensure, as applicable, that the natural gas it intends to sell or deliver to the distributor meets the transporter's quality standards and can be mixed without inconvenience with the distributor's other supplies;
- 7. hold, as applicable, all required contracts with the transporter(s) so that the natural gas sold or delivered to the distributor is moved to the transporter's delivery point in the province of origin or to the delivery point in the distributor's territory during the contract period agreed upon with the latter;
- 8. acknowledge the distributor's exclusive right to manage prudently and diligently the daily allocation of natural gas volumes carried in its distribution system, giving priority to the interest of all its customers over the interest of a particular customer;
- 9. when supplying gas from renewable sources to the distributor, ensure all of the following:
  - a. Sell or deliver to the distributor gas from renewable sources according to the Act of the Régie de l'énergie;

- b. Declare to the distributor where the gas from renewable sources intends to sell or to deliver to the distributor, either in Quebec or outside Quebec;
- c. Provide, on request, all supporting documents required by the distributor demonstrating the contractual chain of acquisition of gas from renewable sources from the producer to the customer, allowing in particular to establish the organic origin of the gas from renewable sources, the physical connection to the gas system in North America and the volumes delivered.

### 11.2.3.6 Gas Quality

The monthly average gross heating value of the natural gas delivered shall be at least 36.00 MJ/m³ unless the customer and the distributor agree on a lower value.

### 11.3 Make-Up Gas Service

### 11.3.1 APPLICATION

For any customer that qualifies for distribution service  $D_5$ : Interruptible and that wishes to purchase from or supply to the distributor, from time to time, the natural gas it withdraws at its facilities, provided the minimum volume of make-up gas withdrawn during the contract period, at a single metering point, divided by the number of days in the contract period is 3,200 m<sup>3</sup>/day.

A customer may use the make-up gas service for the following uses:

- "Competitive Make-up Gas" service to temporarily withdraw a greater volume of gas;
- 2. "Make-up Gas to Avoid an Interruption" service.

### 11.3.2 RATE

A customer who uses the distributor's "Make-up Gas" service is billed, as applicable, the price of the supply of natural gas supplied from time to time to serve it for the quantity of make-up gas delivered for its needs.

A customer who supplies its own natural gas, with or without transfer of ownership, is subject to the provisions of Article 11.2.2.

A customer who uses the make-up gas service is billed, as applicable, the price of the transportation provided from time to time by the distributor to serve it.

A customer who uses the "Competitive Make-up Gas" service is billed the price of load balancing provided from time to time by the distributor to serve it.

A customer who uses the "Make-up Gas to Avoid an Interruption" service is not billed for the load balancing.

A customer who uses the make-up gas service is subject to the provisions of Article 14.4, with the exception of Article 14.4.1 which is replaced by Article 11.3.1.

### 11.3.3 TERMS AND CONDITIONS

### 11.3.3.1 Daily Contract Volume (DCV)

The DCV for the make-up gas service is equal to the estimated average daily volume for the period of the make-up gas deliveries.

A customer using the "Make-up Gas to Avoid an Interruption" service must agree to deliver to, or contract from the distributor, on the scheduled interruption day, a DCV equal to its load for that same day. If the consumption for the scheduled interruption day is different than the agreed DCV, the customer's DCV will be equal to its load on the scheduled interruption day.

On a scheduled interruption day, the customer using the "Competitive Make-up Gas" who wishes to withdraw volumes of natural gas exceeding the agreed upon DCV for this service must agree to deliver to, or contract from the distributor, during that day, an additional DCV equal to its excess load. The provisions related to the excess portion of consumption are identical to those governing the "Make-up Gas to Avoid an Interruption" service.

The provisions governing adjustments to make-up gas service DCVs are identical to those governing natural gas supply service with or without transfer of ownership.

#### 11.3.3.2 Volume Imbalances

The provisions governing the make-up gas service volume imbalances are identical to those governing natural gas supply service with or without transfer of ownership; the make-up gas service DCV is added to the DCV for natural gas supply service, with or without transfer of ownership, for the monitoring of volume imbalances.

### 11.3.3.3 Prior Notice of Use

Deliveries under make-up gas service shall only be permitted when it is economic and operationally possible for the distributor to provide them or to agree to them.

A customer who wishes to avail itself of the make-up gas service must notify the distributor thereof as soon as possible and no later than 10:00 a.m. (ET) on the day preceding the day on which the make-up gas service would begin. On shorter notice, the customer may avail itself of make-up gas service only if the distributor agrees to it.

### 11.3.3.4 Contract Term

The term for written make-up gas service contracts may be less than 12 months.

### 11.4 CONTRIBUTION TO GREENING THE GAS SYSTEM

### 11.4.1 APPLICATION

For any customer whose percentage of gas from renewable sources consumption is less than the percentage of gas from renewable sources imposed by the *Regulation respecting the quantity of gas from renewable sources to be delivered by a distributor*. As of December 1, 2023, it is set at 2%.

### 11.4.2 RATE FOR CONTRIBUTION TO GREENING THE GAS SYSTEM

For each  $m^3$  of volume withdrawn of natural gas, the price of the contribution to the greening of the gas system, as of December 1, 2023, is  $0.000\phi/m^3$ .

### 12. TRANSPORTATION

### 12.1 DISTRIBUTOR'S SERVICE

### 12.1.1 APPLICATION

For any customer who wishes to purchase from the distributor the transportation service needed to move to the distributor's territory the natural gas it withdraws at its facilities.

### 12.1.2 TRANSPORTATION RATE

### 12.1.2.1 Transportation Price

The transportation prices may be periodically adjusted to reflect actual cost of acquisition.

### 12.1.2.1.1 Transportation Basis Price

For each m<sup>3</sup> of volume withdrawn, the transportation basis price, as of December 1, 2023, is 3,212 ¢/m<sup>3</sup>.

### 12.1.3 MINIMUM ANNUAL OBLIGATION (MAO)

The volume withdrawn during each contract year must be at least equal to the MAO applicable for the same period.

### 12.1.3.1 Establishment of MAO - Distribution Rate D1 and D5 Customers

The MAO applicable for each contract year is that agreed upon in the distribution service.

### 12.1.3.2 Establishment of MAO - Distribution Rate D3 and D4 Customers

### For the first contract year

The MAO is equal to the projected volume, agreed upon with the customer, multiplied by 78%.

### For each subsequent contract year

The MAO is equal to the volume for the 12 months of previous year multiplied by 78%.

When the volume for the 12 months of the previous year is less than the MAO defined for the same 12 months, this latter MAO, multiplied by 78%, becomes the current year MAO.

Where, for the current year, a projected volume has been agreed upon with the customer and the volume exceeds both the previous year's volume and the MAO defined for the same year, the current year MAO is equal to the projected volume, agreed upon with the customer, multiplied by 78%.

### 12.1.3.3 Billing of the Volume Deficit

If, at the end of a contract year, a customer has withdrawn a volume that is less than its MAO, transportation service will be billed for the volume deficit at the price stipulated in Article 12.1.2.1.

### 12.1.3.4 Reduction

Except where a customer has replaced natural gas with another energy source, the distributor shall reduce the bill for MAOs if the distributor succeeds in freeing itself, in whole or in part, from its own obligations with respect to the transportation service.

### 12.1.3.5 Revision of MAO Following Implementation of Energy Efficiency Measure

Notwithstanding the foregoing, when a Distribution Rate  $D_3$  or  $D_4$  customer participates in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), a new projected annual volume is established. The

new projected annual volume is equal to the volume used to calculate the MAO (initial volume) less the marginal reduction recognized by the program and is applied from the date the measure is implemented.

A customer wishing to benefit from the reduction of its projected annual volume must so notify the distributor no later than one year after the payment date for the financial assistance.

### For the contract year the measure is implemented

The volume used to calculate the MAO is based on the initial volume and the new projected annual volume prorated in accordance with the volumes withdrawn in the corresponding periods of the year preceding the implementation of the measure.

### For the subsequent contract year

The volume used to calculate the MAO is the new projected annual volume multiplied by 78%.

### 12.1.4 TERMS AND CONDITIONS

### 12.1.4.1 Prior Notice of Entry

A customer who wishes to avail itself of the distributor's transportation service at the earliest on November 1<sup>st</sup> must so notify the distributor in writing before the previous March 1<sup>st</sup>. If less than the required prior notice is given, the customer shall pay for the twelve months following its return to the transportation service a markup of 20% of the price in Article 12.1.2.1. Notwithstanding the above, a customer may avail itself of the distributor's transportation service only if it is possible for the distributor to provide it.

#### 12.1.4.2 Prior Notice of Withdrawal

Subject to Article 12.2.1, a customer who wishes to opt out of the distributor's transportation service, in order to provide the service itself, must so notify the distributor in writing at least 60 days in advance.

Notwithstanding the compliance or not by the customer to the notice required under this Article, the latter may opt out of the distributor's transportation service only if it is possible for the distributor to agree to it.

#### 12.1.4.3 Contract Term

The term for written transportation service contracts must be a minimum of 12 months, except for make-up gas service contracts for which the contract term may be less than 12 months.

### 12.2 CUSTOMER-PROVIDED SERVICE

### 12.2.1 APPLICATION

For any customer who wishes to provide the distributor with the transportation service needed to move to the distributor's territory the natural gas it withdraws at its facilities.

Subject to Article 17.2.2, only Distribution Rate  $D_1$ ,  $D_3$  and  $D_4$  customers may provide the distributor with their own transportation service. In addition, Northern Zone customers must still use part of the distributor's transportation service.

### 12.2.2 RATE

### 12.2.2.1 Distributor's Service Price

The transportation prices may be periodically adjusted to reflect actual cost of acquisition.

### 12.2.2.1.1 Transportation Basis Price

For each m<sup>3</sup> of volume withdrawn, the transportation basis prices, as of December 1, 2023, are as follows:

Southern Zone
0.000¢/m³
0.090¢/m³

### 12.2.3 TERMS AND CONDITIONS

### 12.2.3.1 Assignment of Transportation Capacity held by the Distributor

A customer who wishes to opt out of the distributor's transportation service shall be permanently assigned the transportation capacity already held for it by the distributor. Subsequently, the customer shall pay the transporter directly for the transportation service thus acquired.

Exceptionally, however, a customer who wishes to opt out, in whole or in part, of the distributor's transportation service to purchase gas from renewable sources produced within the distributor's franchise shall not be assigned the transportation capacity for this portion of its consumption. However, where the customer ceases its consumption of gas from renewable sources produced within the firm on a shorter period than 60 months shall be permanently assigned the transportation capacity for the residual period.

Notwithstanding the preceding paragraph, and to the extent that it is economic and operationally possible for the distributor to agree to it, Distribution Rate  $D_1$ ,  $D_3$  or  $D_4$  customers may provide their transportation service directly, after having submitted a request to the distributor within the time limits stipulated in Article 12.2.3.2.

### 12.2.3.1.1 Term of Assigned Transportation Contracts

The transportation capacity assigned to a customer will come from the distributor's Firm Transportation contracts with TransCanada PipeLines Limited or Enbridge Gas Limited. The term of the transportation capacity assignment is 5 years.

### 12.2.3.1.2 Calculation of Assigned Capacity

The capacity assigned to a customer will be equal to the customer's total annual requirements. The capacity assigned to meet the customer's total annual requirements is the maximum of the actual annual volume of the previous year, the forecasted annual volume of the previous year and the forecasted annual volume of the next year.

### 12.2.3.1.3 Subsequent Assignment of Assigned Capacity

A customer who is assigned the transportation capacity held for it by the distributor may in turn assign the capacity to a third party. When the customer decides to permanently dispose of assigned capacity by returning it directly to the transporter, it must first offer it to the distributor. The customer must ensure that any subsequent assignee of such capacity is subject to the same obligation.

### 12.2.3.1.4 Management of Assigned Capacity

A customer who is assigned transportation capacity shall be responsible for managing any increase or decrease required to meet its needs.

### 12.2.3.2 Prior Notice of Entry

A customer who wishes to provide its transportation service must so notify the distributor in writing at least 60 days in advance.

Notwithstanding the compliance or not by the customer to the notice required under this Article, the latter may provide its transportation service only if it is possible for the distributor to agree to it.

### 13. LOAD BALANCING

### 13.1 DISTRIBUTOR'S SERVICE

### 13.1.1 APPLICATION

For any customer who wishes to purchase from the distributor, in whole or in part, the load-balancing service needed to manage on a daily basis the natural gas it withdraws at its facilities.

### 13.1.2 LOAD-BALANCING RATE

The load-balancing price may be periodically adjusted to reflect the actual cost of load balancing tools.

### 13.1.2.1 Price for Customers whose Annual Volume is Less than 75,000 m<sup>3</sup>

For each m<sup>3</sup> of volume withdrawn, the unit price is 4.189¢/m<sup>3</sup>.

Notwithstanding the above, a Distribution Rate  $D_1$  customer who opts out of the distributor transportation service in accordance with Article 17.2.2 is subject to the load balancing price stipulated in Article 13.1.2.2.

### 13.1.2.2 Price for Other Customers and for Customers Subject, as of September 30, 2012, to Article 13.1.2.2 of *Conditions of Service and Tariff* in Effect as of December 1, 2010

For each m³ of volume withdrawn, excluding "Competitive Make-up Gas" and "Make-up Gas to Avoid an Interruption" volumes, the unit price in ¢/m³ is calculated as follows:

$$\left[ \left( \frac{1}{LF} - 1 \right) \times 2.000 \right] + 0.225$$

Where:

**LF:** Load Factor = 
$$\frac{\text{Annual average daily load (A)}}{\text{Peak daily load (P)}}$$

The calculation of the  $\bf A$  and  $\bf P$  parameters is detailed in Article 13.1.3. For  $D_5$  distribution service customers, the  $\bf A$  and  $\bf P$  parameters used in the formula are the parameters modified to take account of the interruption days.

However, the price may not be greater than 18.221¢/m<sup>3</sup>.

### 13.1.2.3 Average Price

Article 13.1.2.2 does not apply when the firm or interruptible service volume withdrawn between October 1, 2022 and September 30, 2023 is nil or does not represent 12 consecutive months of consumption.

These customers will be subject to an average unit price based on their distribution rate, in accordance with the following table:

Distribution	Price
Rate	¢/m³
<b>D</b> <sub>1</sub>	4.189
$D_3$	1.563
D <sub>4</sub>	0.899
D <sub>5</sub> – Category A	(0.669)
D₅ – Category B	3.106

### 13.1.2.4 Contract Change

The load balancing price will be revised during the year, following any contract change to the distribution service  $D_5$ : Interruptible resulting in a sub-rate or category change, or if the customer transfers from firm service to interruptible service or vice versa.

The price will be set in accordance with the terms and conditions set forth in Articles 13.1.2.1 to 13.1.2.3, as applicable, based on the volume from October 1, 2022 to September 30, 2023.

### 13.1.2.5 Load Balancing Service Settlement

A load balancing service settlement is billed when:

- 1. a customer ceases to use the distributor's load balancing service. The settlement is calculated at the moment it ceases to use the distributor's service as follows:
  - a) Price based on volume of 12 months preceding the cessation of service, in accordance with Article 13.1.2.2, multiplied by the volume of the 12 months preceding the cessation; less
  - b) Total amounts billed for load balancing during the 12 months preceding the cessation.
- 2. a customer subject to Articles 13.1.2.2 and 13.1.2.3 requests settlement. The settlement is calculated as of September 30, 2023 as follows:
  - a) Price based on volume from October 1, 2023 to September 30, 2024, in accordance with Article 13.1.2.2, multiplied by the volume from October 1, 2023 to September 30, 2024; less
  - b) Total amounts billed for load-balancing from October 1, 2023 to September 30, 2024.

To take advantage of this option, the customer must have, at the time of the settlement calculation, a history of consumption as well as consumption of more than 75,000 m³ for the period of October 1, 2023 to September 30, 2024.

The request must be sent in writing to the distributor before the beginning of the reference period used for the calculation of the settlement. The customer then remains subject to the load-balancing service settlement for a minimum of three years. Similarly, if the customer withdraws from this option, he must wait another three years to avail himself of it.

For any customer subject to Article 13.1.2.2 who requests a settlement, a load-balancing service settlement will be billed based on the volume from October 1, 2022 to September 30, 2023, in accordance with Article 13.1.2.2, in the case of a debit balance only.

### 13.1.3 CALCULATION OF PARAMETERS

Subject to Articles 13.1.2.1 and 17.2.3, the consumption parameters shall be calculated as follows:

### 13.1.3.1 Parameters for Distribution Rates D<sub>1</sub>, D<sub>3</sub> and D<sub>4</sub> customers

- **A** = Volume from October 1, 2022 to September 30, 2023 # days from October 1, 2022 to September 30, 2023
- **P** = Maximum daily load from December 1, 2022 to February 28, 2023

For Distribution Rates  $D_1$  and  $D_3$  customers except customers subject to rate combination  $D_3$ - $D_5$ , the maximum daily load for the winter months is estimated as follows:

 $\mathbf{P} = (MaxDL) \times multiplier$ 

where: **MaxDL** = Highest of the average daily loads of each month from December 2022 to February 2023

where: **multiplier** = Maximum  $(2.1 - (1.1 \times A \div MaxDL); 1)$ 

### 13.1.3.2 Parameters for Distribution Rate D<sub>5</sub> Customers

Parameters **A** and **P** are modified as follows to consider interruption days:

```
A = Volume from October 1, 2022 to September 30, 2023 X (No. days from October 1, 2022 to September 30, 2023 – MaxD)

No. days from October 1, 2022 to September 30, 2023 – ActualD)

(No. days from October 1, 2022 to September 30, 2023 – ActualD)
```

 $\mathbf{P} = \text{Maximum daily load from December 1, 2022 to February 28, 2023 } \mathbf{x} \text{ maximum } (\underline{76 - \text{MaxD}}; 0)$ 

76

where: **MaxD** = Maximum number of interruption days referred to in Article 14.4.6, subparagraph 1 where: **ActualD** = Actual number of interruption days from October 1, 2022 to September 30, 2023

Volumes withdrawn under "Competitive Make-up Gas" service or "Make-up Gas to Avoid an Interruption" service are not considered in the parameter calculations.

### 13.1.4 MINIMUM ANNUAL OBLIGATION (MAO)

Article 13.1.4 does not apply to customers subject to rate DT or to rate Dual-Energy for small and medium power for Hydro-Québec space heating.

Any customer with a load factor of less than 10% and a peak capacity demand greater than or equal to 10,000 m<sup>3</sup> in a given rate year will be subject to this article in the following rate year:

- For customers who were not subject to this section in the previous rate year, the distributor considers the actual peak and the actual consumption volume in order to determine whether they will be subject to this section in the following rate year;
- For customers subject to the previous rate year, the distributor considers the potential peak, as defined in Article 13.1.4.1, and the actual consumption volume to determine liability for the following rate year.

Notwithstanding the foregoing, the distributor may agree to an MAO with a customer migrating to Rate  $D_1$  or a new customer, if it anticipates that the customer's consumption parameters would meet the eligibility criteria. If the customer begins using Rate  $D_1$ :

• no later than the last day of February, they will be subject to the MAO for the current rate year. In this case, the volume used to calculate the load factor is determined as follows:

after the last day of February, they will be subject to the MAO for the following rate year.

For all subject customers, the sum of amounts billed for transmission and balancing must be at least equal to the applicable MAO for the same period.

### 13.1.4.1 Establishing the MAO

For customers of the distributor's transmission service, the amount of the MAO is determined according to the following formula:

```
MAO amount = 1,197.896¢/m³ x Customer's potential peak x 75%
```

For customers who provide their own transport service, the MAO amount is determined according to the following formula:

```
\begin{bmatrix} \textit{Customer's potential peak} - \frac{\textit{Volume from October 1,2022 to September 30, 2023}}{\textit{\# days from October 1,2022 to September 30,2023}} \end{bmatrix} x 75\%
```

The customer's potential peak is determined using the following formula:

```
Potential peak = Max (Real peak t-1; Potential peak agreed with customer) + 2

* Max (Real peak t-Max (Real peak t-1; Potential peak agreed with customer); 0)
```

The actual peak for year t corresponds to the maximum daily consumption from December 1 to the last day of February of tariff year t.

For customers for whom the distributor does not have billable daily data, actual daily peaks will be estimated using the formula defined in article 13.1.3.1.

### 13.1.4.2 Invoicing of loss-making income

If, at the end of the tariff year, the customer has been billed for transmission and balancing at an amount lower than its MAO, it will be billed for the shortfall.

### 13.1.5 PROCESSING OF DELIVERIES

### 13.1.5.1 Adjustment Charges for Non-uniform Delivery

For customers subject to the load balancing price stipulated in Article 13.1.2.2, who supply the distributor with the natural gas and who purchase from the distributor the transportation used to bring the natural gas they withdraw at their facilities to the distributor's territory, an adjustment charge shall be billed at the end of the supply contract period. Customers may choose between the following two billing methods:

- 1. deferral of adjustement costs over the 12 months of the next contract period; or
- 2. financial settlement of adjustment charges at the end of the contract period; customers who change the services they purchase from the distributor or a customers who benefits from the equal payments plan as defined in Article 7.2.3 during the year of the supply contract must always financially settle the adjustment charges at the end of the contract period.

The choice must be notified in writing to the distributor before the start of the supply contract. If this election is not notified within the time limit, the adjustment costs will be paid at the end of the contract period.

The value of the balancing charge is equal to the price impact generated by the daily differences between the DCV and the TUD based on the balancing charge calculation period beginning on the anniversary date of the supply contract and ending on the anniversary date of the contract the following year. The TUD is established as follows:

**TUD** = theoretical uniform delivery for the calculation period (sum of DCVs in the calculation period ÷ # days in the calculation period)

The excess DCV over the TUD is purcharsed by the distributor, and the shortfall of DCV over the TUD is sold to the customer at the following price:

- from 0% to 2% of the TUD, at the distributor's average natural gas supply price during the calculation period:
- the lesser, in the case of an average of more than 2% of TUD, or the greater, in the case of a shortage, of:
  - o the distributor's average natural gas supply price during the calculation period, and
  - o the market price at the time the discrepancy occurred.

### 13.1.5.1.1 Allocation in Customer Groupings

Adjustment charges for all customers in a customer grouping, if any, are allocated to each of the customer in proportion to their respective volumes withdrawn during the Contract Period. Adjustment costs are then billed individually to customers.

### 13.1.5.2 Volume Transposition

For customers who supply the distributor with the transportation used to bring to the distributor's territory the natural gas they withdraw at their facilities, the load balancing price defined in Article 13.1.2.2 must be calculated on the basis of a transposed consumption profile established as follows, subject to Article 17.2.3:

TL = L + TUD - DCV

where: **TL** = Transposed Load (monthly or daily, as the case may be)

**L** = Load (monthly or daily, as the case may be)

**TUD** = Theoretical Uniform Delivery (sum of the DCVs from October 1, 2022 to September 30, 2023

÷ # days from October 1, 2022 to September 30, 2023 having a DCV)

**DCV** = Daily Contract Volume

The TUD and DCVs are calculated on a monthly basis for customers without daily readings.

### 13.1.6 TERMS AND CONDITIONS

### 13.1.6.1 Prior Notice of Entry

A customer who wishes to avail itself of the distributor's load balancing service must so notify the distributor in writing at least 60 days in advance. Notwithstanding the required prior notice, the customer may avail itself of the distributor's load balancing service only if it is possible for the distributor to provide it.

### 13.1.6.2 Prior Notice of Withdrawal

The customer who wishes to opt out of the distributor's load balancing service, in order to provide the full service itself, must so notify the distributor in writing at least 60 days in advance. On shorter notice, the customer may opt out of the distributor's load balancing service only if it is possible for the distributor to agree to it.

#### 13.1.6.3 Contract Term

The term for written load balancing service contracts must be a minimum of 12 months, except for make-up gas service contracts for which the contract term may be less than 12 months.

### 13.2 CUSTOMER-PROVIDED SERVICE

### 13.2.1 APPLICATION

For any customer who wishes to provide, in whole or in part, with the load balancing service needed to manage on a daily basis the natural gas it withdraws at its facilities or it injects in the distribution system subject to Article 17.2.2.

A customer subject to Rate  $D_1$ ,  $D_3$  or  $D_4$  who wishes to provide its full load balancing service shall agree to deliver to the distributor each day a DCV equal to its load for that same day; the terms and conditions shall be those relative to volume imbalances stipulated under the "Customer-Provided Service" Article under Supply Service.

A customer subject to Rate  $D_R$  is subject to Article 13.2.2.2 "Differences Between Nominated Volumes and Volumes Injected" excepted of the customer injecting gas from renewable sources who deliver all their injected volumes free of charge and whose daily injection volume is less than 10,000 GJ.

### 13.2.2 RATE

### 13.2.2.1 Service Price

The customer shall not be billed for the price of the load balancing service it provides for itself in whole or in part.

### 13.2.2.2 Differences Between Nominated Volumes and Volumes Injected

The charges for differences between nominated volumes and volumes injected are as follows:

### **Daily imbalances**

No charges shall be required if the daily difference between the nominated volume and the volume injected is less than the greater of 75 GJ or 2% of the total nominated volume at a receipt point or the greater of 75 GJ or 2% of the total nominated volume in the consumption zone.

In the case where the daily difference between the nominated volume and the volume injected is higher than the greater of 75 GJ or 2% in the consumption zone and at a receipt point:

- 1. no charges shall be required if the daily difference between the nominated volume and the volume injected at that receipt point by a customer is in the sense opposite to the daily difference between nominated volumes and volumes injected in the consumption zone;
- 2. charges shall however be required when this difference is in the same sense as the daily difference in the consumption zone.

In the latter case, the daily imbalance of the consumption zone shall be allocated among all customers having a billable daily imbalance, in proportion to their individual imbalance in excess of the greater of 75 GJ or 2% of their nomination.

The daily imbalance prices are as follows:

Difference	First 2% to 4%	Next 4% to 8%	Next 8% to 10%	Next exceeding 10%
Price (¢/m³)	1.099	2.746	4.119	5.493

### Cumulative difference account balance

The cumulative difference account balance shall be calculated by adding or deducting any daily difference to the previous cumulative difference account balance. This balance may be reduced in accordance with Article 14.5.8.

Charges shall be payable if the cumulative daily account balance is higher than the greater of 150 GJ or 4% of the greater of the nominated volumes or the average nominated volumes for the past 30 days.

The prices applicable to the cumulative differences are as follows:

Balance	First 4% to 6%	Next exceeding 6%
Price (¢/m³)	0.824	1.373

These prices may be periodically adjusted to reflect modifications to TransCanada PipeLines rates.

### 13.2.3 TERMS AND CONDITIONS

### 13.2.3.1 Prior Notice of Entry

A customer who wishes to provide its full load balancing service must so notify the distributor in writing at least 60 days in advance. On shorter notice, the customer may provide full load balancing service only if it is possible for the distributor to agree to it.

### 14. DISTRIBUTION

### **14.1** GENERAL PROVISIONS

### 14.1.1 RIGHT TO MOST ADVANTAGEOUS RATE

A customer is entitled to the most advantageous distribution rate according to the following conditions:

- the distribution rate must be agreed upon for the entire term of the written contract, subject to subsequent amendments, agreed to by the parties, to the subscribed volume, the minimum annual obligation (MAO) and the agreed upon price;
- 2. A customer who has a verbal contract may change distribution rates on agreement with the distributor.

### 14.1.2 DEFAULT DISTRIBUTION RATE

Rate  $D_1$  applies by default except in the case of customers who inject natural gas in the distribution system for whom Rate  $D_R$  applies by default.

### 14.1.3 CONTRACT TERM

The term for all written contracts must be a minimum of 12 months, except for make-up gas service contracts for which the contract term may be less than 12 months.

### 14.1.4 CUSTOMER GROUPINGS

Customer groupings are not permitted for distribution service.

### 14.1.5 SUBSEQUENT ADJUSTMENTS

The distribution rates are subject to rate modifications ordered by the Régie de l'énergie after they come into force to reflect any change in operating costs arising from the decision of a competent authority (legislator, governments, public agencies) ("fait du prince").

### 14.2 DISTRIBUTION SERVICE D<sub>1</sub>: GENERAL

### 14.2.1 APPLICATION

For any customer intending to withdraw, at its facilities, natural gas that must be moved within the distributor's territory.

For all withdrawals of firm service natural gas measured at a single metering point. A customer may not, from a single metering point, withdraw natural gas simultaneously under Rate  $D_1$  and under another Distribution Rate.

### 14.2.2 DISTRIBUTION RATE D<sub>1</sub>

### 14.2.2.1 Basic Fee

The basic fees per metering device depend on annual volume withdrawn as follows:

	Volume Withdrawn			Price
	r	m³/Year		¢/Metering device/Day
from	0	to	10,950	62.064
from	10,950	to	36,500	126.460
from	36,500	to	109,500	150.839
from	109,500	to	365,000	159.184
from	365,000	to	1,095,000	208.787
from	1,095,000	to	3,650,000	275.111
	3,650,000		and over	684.327

The price is then multiplied by the number of days of the billing period.

### 14.2.2.2 Unit Prices for the Volume Withdrawn

For each m<sup>3</sup> of volume withdrawn at the levels below multiplied by the number of days in the billing period, the unit prices are as follows:

Volume Withdrawn m <sup>3</sup> /Day						Price ¢/m³
firs	30	from	0	to	30	
		-	-			31.070
next	70	from	30	to	100	21.220
next	200	from	100	to	300	18.339
next	700	from	300	to	1,000	13.894
next	2,000	from	1,000	to	3,000	10.286
next	7,000	from	3,000	to	10,000	7.226
next	20,000	from	10,000	to	30,000	5.820
next	70,000	from	30,000	to	100,000	4.829
m³ exceeding 100,000 1			100,000		and over	3.998

### 14.2.3 RATE REBATES

### 14.2.3.1 Rate Rebate to Compete with Dual Energy

If required by the competitive situation, the distributor and the customer may agree, within the limits of the dual energy section of the Rate Flexibility Program, a copy of which is available upon request, to a percentage reduction applicable to the Distribution Rate.

### 14.2.4 MINIMUM ANNUAL OBLIGATIONS (MAO)

### 14.2.4.1 MAO - Newly connected or financially assisted customer

14.2.4.2 The distributor may agree, with a customer whose service address is newly connected to the distribution system or with a customer who receives financial assistance, on an MAO for the entire contract term. If, at the end of a contract year, the customer has withdrawn a volume that is less than its MAO, it will be billed for the volume deficit at the lower of the average price of the Distribution Rate paid during the 12 months of the contract year or of the average price of the Distribution Rate resulting from the billing of the volume deficit uniformly distributed over the contract year.

### 14.2.4.3 MAO - Customers using natural gas as a back-up energy source

Article 14.2.4.2 does not apply to customers subject to Rate DT or to dual-energy rates for small and medium power for Hydro-Québec space heating.

Any customer with a load factor of less than 10% and a peak capacity demand greater than or equal to 10,000 m<sup>3</sup> in a given rate year will be subject to this Article in the following rate year:

• For customers not subject to the previous rate year, the distributor considers the actual peak and the actual consumption volume to determine their liability for the following rate year;

For customers subject to the previous rate year, the distributor considers the potential peak, as
defined in Article 14.2.4.2.1, and the actual consumption volume to determine liability for the following
rate year.

Notwithstanding the foregoing, the distributor may agree to an MAO with a customer migrating to rate  $D_1$  or a new customer, if it anticipates that the customer's consumption parameters would meet the eligibility criteria. If the customer begins using Rate  $D_1$ :

• by the last day of February at the latest, it will be subject to MAO for the current tariff year. In this case, the volume used to calculate the utilization coefficient is determined as follows:

Nomber of days in the rate year

Actual volume consumed \*  $\frac{1}{Nomber\ of\ days\ between\ the\ start\ of\ consumption\ at\ D_1\ and\ the\ end\ of\ the\ tariff\ year}$ 

after the las day of February, it will be subject to MAO in the following tariff year.

For all liable customers, the amount billed for distribution must be at least equal to the applicable MAO for the same period. période.

### 14.2.4.3.1 Establishing the MAO

The MAO amount is determined according to the following formula:

```
MAO amount = 723.598 \text{¢/m}^3 x Potential customer peak x 75\%
```

The customer's potential peak is determined using the following formula:

```
Potential peak = Max (Real peak t-1; Potential peak agreed with customer) + 2
* Max (Real peak t-Max (Real peak t-1; Potential peak agreed with customer); 0)
```

The actual peak for year t corresponds to the maximum daily consumption from December 1 to the last day of February of tariff year t.

For customers for whom the distributor does not have billable daily data, actual daily peaks will be estimated using the formula defined in Article 13.1.3.1.

### 14.2.4.3.2 Invoicing of loss-making income

If, at the end of the rate year, the customer has been billed for less than his MAO, he will be billed for the shortfall.

### 14.3 DISTRIBUTION SERVICES D3 AND D4: STABLE LOAD

### 14.3.1 APPLICATION

For any customer intending to withdraw at its facilities, natural gas that must be moved within the distributor's territory.

### Distribution service D<sub>3</sub>

For all withdrawals of firm and stable service natural gas measured at a single metering point when the customer's subscribed volume is at least 333 m $^3$ /day, when the customer's load factor, calculated as an A / P ratio according to the non-transposed parameters defined in the load balancing service, is at least 60% and when the annual volume of natural gas is at least 75,000 m $^3$ . A customer may, at a single metering point, withdraw natural gas simultaneously under Rate D $_3$  and under Rate D $_5$ .

### Distribution service D<sub>4</sub>

For all withdrawals of firm and stable service natural gas measured at a single metering point when the customer's subscribed volume is at least  $10,000 \text{ m}^3/\text{day}$ . A customer may, at a single metering point, withdraw natural gas simultaneously under Rate  $D_4$  and under Rate  $D_5$ .

Notwithstanding the foregoing, when a Distribution Rate  $D_3$  or  $D_4$  customer participates in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), the aforementioned threshold can be reduced to take into account the marginal reduction recognized by the program for the average length of time the efficiency measure is implemented. Where applicable, the new threshold is equal to the subscribed volume before the measure was implemented, less a volume equal to the daily marginal reduction recognized by the program.

### 14.3.2 DISTRIBUTION RATES D<sub>3</sub> AND D<sub>4</sub>

### 14.3.2.1 Minimum Daily Obligation

For each m<sup>3</sup> of subscribed volume at the levels indicated below, the unit prices are as follows:

	Subscribed Volume m³/Day					<b>Price</b> ¢/m³/Day
first	333	from	0	to	333	11.485
next	667	from	333	to	1,000	9.248
next	2,000	from	1,000	to	3,000	6.312
next	7,000	from	3,000	to	10,000	5.232
next	20,000	from	10,000	to	30,000	3.834
next	70,000	from	30,000	to	100,000	2.997
next	200,000	from	100,000	to	300,000	2.138
next	700,000	from	300,000	to	1,000,000	1.728
m³ exce	eding 1,000,000		1,000,000		and over	1.176

The result of the calculation is multiplied by the number of days in the billing period.

### 14.3.2.2 Unit Price for the Volume Withdrawn up to the Subscribed Volume

For withdrawals up to the subscribed volume multiplied by the number of days in the billing period for a customer without daily readings and for daily withdrawals up to the subscribed volume for a customer with daily readings, the unit price is  $0.350 \text{c/m}^3$ .

### 14.3.2.3 Reduction According to Contract Term

The average unit price calculated pursuant to Articles 14.3.2.1 and 14.3.2.2 may be reduced by a percentage calculated as follows:

plus, for contract terms longer than 60 months

plus, for contract terms longer than 180 months

60

The maximum percentage reduction is 26%.

### 14.3.2.4 Additional Reductions

In an initial contract negotiated with a customer whose service address is newly connected to the distribution system, the distributor and the customer may agree on a percentage reduction not exceeding 5%, additional to that calculated under Article 14.3.2.3, for the first year only.

A customer with a subscribed volume greater than or equal to 1,000,000 m³/day is entitled to an additional reduction subject to the prior authorization of the Régie de l'énergie.

### 14.3.2.5 Withdrawals in Excess of 100% of the Subscribed Volume

For withdrawals in excess of 100% of the subscribed volume multiplied by the number of days in the billing period for a customer without daily readings, and for daily withdrawals in excess of 100% of subscribed volume for a customer with daily readings:

• The average unit rate for each m³ exceeding the subscribed volume shall be established by means of the rate schedule below, beginning with the level corresponding to the subscribed volume, by weighting of the rates of each m³ in excess of the subscribed volume up to the average daily volume exceeding the subscribed volume.

	Subscribed Volume and Daily Volume m³/Day					<b>Price</b> ¢/m³/Day
first	333	from	0	to	333	18.339
next	667	from	333	to	1,000	13.894
next	2,000	from	1,000	to	3,000	10.286
next	7,000	from	3,000	to	10,000	7.226
next	20,000	from	10,000	to	30,000	5.820
next	70,000	from	30,000	to	100,000	4.829
m³ exce	eding 100,000		100,000		and over	3.998

### 14.3.2.6 Unauthorized Withdrawals

All withdrawals in excess of 150% of the subscribed volume multiplied by the number of days in the billing period for a customer without daily readings and all daily withdrawals in excess of 150% of the subscribed volume for a customer with daily readings, made from November 1 to March 31, are subject to a penalty of 50¢/m³ and to the price of natural gas traded at Iroquois.

For a customer providing its own supply service, unauthorized withdrawal volumes will be added to the sum of the DCVs to determine the volume imbalances for the contract period.

### 14.3.2.7 Negociated Peak Service

The distributor and the customer may agree on a negotiated peak service. The terms and conditions associated with this service are subject to the approval of the Régie de l'énergie.

### 14.3.3 CONTRACT EXTENSION

A Distribution Rate D<sub>3</sub> or D<sub>4</sub> customer may extend its contract by one year and maintain the same reduction for the contract term provided it does so at least the following number of months prior to the expiry of its contract:

Contract Term in Months - 12

2

This time may not exceed 24 months.

### 14.3.4 REVISION OF SUBSCRIBED VOLUME

### 14.3.4.1 By the Customer

Except to replace natural gas by another energy source, a customer may in the course of the contract reduce its subscribed volume by up to 10% beginning with the second year and for each additional year. However, in the case of a new contract, the subscribed volume must at all times remain at least 75% of its initial level during the contract term. The customer must provide written notice of at least three months.

At all times, the customer's subscribed volume must be at least 333  $m^3$ /day under Rate  $D_3$  and 10,000  $m^3$ /day under Rate  $D_4$ .

Notwithstanding the foregoing, the customer is required to comply, as applicable, with the minimum annual obligation terms agreed under Articles 4.3.4 and 14.3.6.

### 14.3.4.2 Following Implementation of an Energy Efficiency Measure

Notwithstanding the foregoing, when a Distribution Rate  $D_3$  or  $D_4$  service customer in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), he is entitled to a reduction of its subscribed volume equal to the daily marginal reduction recognized by the energy efficiency program. In the case of a new contract, the initial subscribed volume may also be reduced by the value of the marginal reduction. This reduction of the subscribed volume will be effective from the date of implementation of the energy efficiency program for which the marginal reduction is recognized.

A customer wishing to benefit from the reduction in its projected annual volume must so notify the distributor no later than one year after the date of payment of the financial assistance.

### 14.4 DISTRIBUTION SERVICE D<sub>5</sub>: INTERRUPTIBLE

### 14.4.1 APPLICATION

For any customer intending to withdraw, at its facilities, natural gas that must be moved within the distributor's territory.

For withdrawals of interruptible service natural gas measured at a single metering point when the sum of the subscribed volume under Rate  $D_3$  or  $D_4$  and 1/365 of the minimum volume for the contract period under interruptible service is at least 3,200 m<sup>3</sup>/day.

Notwithstanding the foregoing, when a Distribution Rate  $D_5$  customer participates in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), the aforementioned threshold referred to below can be reduced to take into account the marginal reduction recognized by the program for the average length of time the efficiency measure is implemented. Where applicable, the new threshold is established using as the minimum volume for the interruptible service contract period the projected annual volume when the measure is implemented, as calculated in Article 14.4.3.3.2, multiplied by the agreed upon minimum annual obligation (MAO) percentage.

To be eligible for this service, the customer must use the distributor's transportation service.

A customer may choose Category A or B, depending on the desired guarantee for availability of service. However, the customer may avail itself of interruptible service under Category B only if it is economic and operationally possible for the distributor to agree to it. Article 14.4.6 indicates the maximum number of interruption days for each Category.

A customer may, at a single metering point, withdraw natural gas simultaneously under Rate  $D_5$  and under Rate  $D_3$  or  $D_4$ . However, a customer cannot withdraw natural gas, at a single metering point, under both Category A and Category B of Distribution Rate  $D_5$  simultaneously.

The distributor and the customer may agree on a maximum daily volume of interruptible service.

### 14.4.2 DISTRIBUTION RATE D<sub>5</sub>

### 14.4.2.1 Unit Prices for the Volume Withdrawn

For each  $m^3$  of volume withdrawn, the unit price is a weighted average calculated on the basis of the sum of the subscribed volume under Rate  $D_3$  or  $D_4$  and 1/365 of the projected interruptible service volume. For a make-up gas service contract, the projected volume is divided by the number of days of the contract period.

This unit price is the result of the distribution of the volumes among the levels below:

For Each m <sup>3</sup> of Subscribed Volume under Firm Service and of Projected Daily Volume under Interruptible Service						Price
		m³/Da	У			¢/m³
first	3,000	from	0	to	3,000	15.286
next	7,000	from	3,000	to	10,000	11.178
next	20,000	from	10,000	to	30,000	9.692
next	70,000	from	30,000	to	100,000	6.446
next	200,000	from	100,000	to	300,000	5.362
m³ exc	m <sup>3</sup> exceeding 300,000 300,000 and over			4.754		

### 14.4.2.2 Reduction According to Minimum Annual Obligation (MAO)

The average unit price calculated pursuant to Article 14.4.2.1 may be reduced by a percentage calculated as follows:

### 14.4.2.3 Reduction According to Contract Term

The average unit price calculated pursuant to Article 14.4.2.1 may be reduced by a percentage calculated as follows:

The reduction according to the contract term is only available when the customer commits to an agreed upon minimum annual obligation (MAO) percentage of at least 25%.

### 14.4.2.4 Additional Reduction

For the initial contract negotiated with a customer whose service address is newly connected to the distribution system, the distributor and the customer may agree on a percentage reduction, not exceeding 15%, additional to those calculated in Articles 14.4.2.2 and 14.4.2.3, for the first year only.

### 14.4.2.5 Unauthorized Withdrawals Exceeding Maximum Daily Volume

All natural gas withdrawals in excess of the maximum daily volume are subject to a penalty of 50¢/m3.

### 14.4.2.6 Unauthorized Withdrawals During Interruptions

All natural gas withdrawals made despite receipt of an interruption notice is subject to a penalty of \$5.00/m3.

If a customer has a stable load service contract, it will pay this penalty on volumes in excess of subscribed volume.

The daily volumes of natural gas withdrawn under "Make-up Gas to Avoid an Interruption" service or "Competitive Make-up Gas" service, up to 102% of the actual delivery of make-up gas during the interruption day are not subject to the penalty of  $$5.00/m^3$ . The supply service terms and conditions are those of Article 11.2.3.3.1.

### 14.4.2.7 Customers considered unable to interrupt

The criterias related to the ability to interrupt are: the use of make-up gas to avoid interruption in past winters, the possession and proper operation of redundancy equipment using an energy source other than natural gas, the existence of an action plan to stop or reduce operations, proof of reservation of make-up gas to avoid interruption for the coming winter, and the length of time a customer can sustain an interruption.

The distributor shall not send any interruption notice to customers considered unable to interrupt during the rate year.

Any withdrawal of natural gas made on days in which the customer would normally have been interrupted should be billed at the higher of the average price of make-up gas to avoid an interruption or the distributor's supply and transportation price.

The terms and conditions set forth in Article 14.4.6, with the exception of the terms and conditions set forth in the first paragraph concerning the determination of the number of days the customer considered unable to interrupt would normally have been interrupted, do not apply to customers covered by this Article.

### 14.4.3 MINIMUM ANNUAL OBLIGATION (MAO)

The volume withdrawn during each contract year must be at least equal to the applicable MAO for the same period.

### 14.4.3.1 Establishment of MAO

The applicable MAO for each contract year is equal to the projected annual volume multiplied by the agreed upon MAO percentage.

At the end of the contract year, the MAO shall be adjusted by subtracting from it an agreed upon daily volume (or, failing that, 1/365 of the projected volume) for each interruption day, including the unauthorized withdrawal days.

### 14.4.3.2 Billing of the Volume Deficit

At the end of the contract year, the volume withdrawn over the contract year shall be adjusted by subtracting from it the volumes withdrawn:

- 1. as unauthorized withdrawals during interruptions;
- 2. under a "Make-up Gas to Avoid an Interruption" contract; and
- 3. under a "Competitive Make-up Gas" contract.

If at the end of a contract year, a customer has withdrawn an adjusted volume that is less than its adjusted MAO, it will be billed for the volume deficit at the price determined in accordance with Articles 14.4.2.1 to 14.4.2.4, taking into account, where applicable, the competition rate adjustment described in Article 14.4.4.

### 14.4.3.3 Revision of MAO

### **14.4.3.3.1** By the Customer

Except to replace natural gas by another energy source, a customer may in the course of the contract reduce its initial MAO up to 20% beginning with the second year and, for each additional year, by an additional 5%. However, the MAO must at all times remain at least 50% of its initial level during the contract term. The customer must provide prior written notice of at least three months for a reduction of 20% or less and at least six months for a reduction of more than 20%.

When the MAO percentage is modified during the contract year, the volume deficit is calculated annually for each agreed upon MAO percentage. The two volume deficits obtained are prorated according to the number of days each MAO percentage was in effect.

Notwithstanding the foregoing, the customer is required to comply, as applicable, with the minimum annual obligation terms agreed under Article 4.3.4.

### 14.4.3.3.2 Following Implementation of an Energy Efficiency Measure

Notwithstanding the foregoing, when a Distribution Rate  $D_5$  customer participates in an energy efficiency program under the Global Energy Efficiency Plan (GEEP), a new projected annual volume is established. The new projected annual volume is equal to the volume used to calculate the MAO (initial projected volume) less the marginal reduction recognized by the program and is applied from the date the measure is implemented.

A customer wishing to benefit from the reduction in its projected annual volume must so notify the distributor no later than one year after the date of payment of the financial assistance.

### For the contract year the measure is implemented

The volume used to calculate the MAO is determined from the initial projected volume and the new projected annual volume prorated in accordance with the volumes withdrawn in the corresponding periods of the year preceding the implementation of the measure.

### For each subsequent contract year

The volume used to calculate the MAO is the new projected annual volume.

### 14.4.4 COMPETITION RATE ADJUSTMENT

The distributor and the customer may agree on a negotiated percentage adjustment applicable to the Distribution Rate calculated in accordance with Article 14.4.2.1.

### 14.4.5 COMBINATION OF RATES D<sub>3</sub> AND D<sub>5</sub> OR D<sub>4</sub> AND D<sub>5</sub>

When a customer withdraws natural gas simultaneously under Rates  $D_3$  and  $D_5$  or  $D_4$  and  $D_5$ , at a single metering point, the volume withdrawn during a day is first considered as volume withdrawn under Rate  $D_3$  or  $D_4$  up to the limit of the subscribed volume. The volume is subsequently considered withdrawn under Rate  $D_5$ .

### 14.4.6 INTERRUPTIONS

1. The distributor must, on an annual basis, give service priority to interruptible customers in ascending order of subrates and, to the extent possible, within each of the subrates in descending order of prices, while complying with the maximum number of interruption days.

The maximum number of interruption days is determined in accordance with the following table:

Sum of Subscribed Volume under Firm Service and Projected Daily Volume under Interruptible Service				Number of tion Days*
Subrate D₅	Between m³/Day	and m³/Day	Category A	Category B
5.5	3,000	10,000	61	20
5.6	10,000	30,000	61	20
5.7	30,000	100,000	44	30
5.8	100,000	300,000	62	30
5.9	300,000	and over	67	30

<sup>\*</sup> Applicable up to the limit of the projected volume

Notwithstanding 1. above, "Competitive Make-Up Gas" service customers are the first to be notified of an
interruption day. These customers must then limit their withdrawals to the volume they are committed to
deliver (DCV) during the planned interruption day;

The maximum number of days of limited consumption is 67 days;

3. Until otherwise notified, the customer must cease or decrease, as the case may be, its withdrawals of natural gas to the extent determined by the distributor, at the date and time indicated on the interruption

notice received from the distributor. The distributor must give such interruption notice at least 2 hours before the beginning of the interruption;

- 4. Except for the "Competitive Make-Up Gas" service, natural gas service must be interrupted at least one full day per year;
- 5. Each year, the distributor must send to all its interruptible customers a copy of its interruption policy; a copy of the policy is also available to any customer who requests it.
- In case of default by the customer to comply with the interruption notice issued by the distributor, the latter can proceed to an interruption at the service address without it being required to notify the customer in more details.

### 14.4.7 CONTRACT EXTENSION

A customer may extend its contract by one year and maintain the same reduction for the contract term provided it does so at least the following number of months prior to the expiry of its contract:

Contract Term in Months - 12

2

The time cannot exceed 24 months.

### 14.5 RECEIPT SERVICE DR

### 14.5.1 APPLICATION

For a customer who wishes to inject natural gas produced in the territory served by the distributor into the distributor's gas system.

### 14.5.2 RECEIPT RATE

The receipt rates may be periodically adjusted to reflect actual cost.

### 14.5.2.1 Prices at Receipt Points

### 14.5.2.1.1 Minimum Daily Obligation

For each m³ of maximum contractual capacity (MCC), the unit prices shall be as follows, depending on the receipt point:

Receipt Point	Price – Investments section (¢/m³/day)	Price - Distribution section (¢/m³/day)
Saint-Hyacinthe	0.329	0.382
Coop Agri-Énergie Warwick	0.000	0.898
ADM Agri-Industries Company	0.401	1.275
СТВМ	1.027	2.338
SÉMECS	0.000	0.452
WAGA (Saint-Étienne-des-Grès)	0.000	0.532
WAGA (Chicoutimi)	0.000	0.016

### 14.5.2.1.2 Unit Prices for the Volume Injected

For each m<sup>3</sup> of volume injected, the unit price shall be 0.178¢/m<sup>3</sup>.

### 14.5.2.2 Prices at Delivery Points for Customer who Injects Natural Gas

### 14.5.2.2.1 Unit Prices for Volumes Delivered Within the Territory

For each m<sup>3</sup> of volume delivered within the territory, the unit prices shall be as follows, based on the consumption zone:

Consumption Zone	Price (¢/m³)
Estrie	0.000
Montérégie	0.000
Bécancour	0.000
Saguenay	0.000

### 14.5.2.2.2 Unit Price for Volumes Delivered Outside the Territory

For each m<sup>3</sup> of volume delivered outside the territory, the unit price shall be 0.700¢/m<sup>3</sup>.

### 14.5.3 CONTRACT RENEWAL AND INDEMNITY

The contract concluded with the customer may include a clause by which it is automatically renewed at its expiry or a clause requiring the customer to pay the distributor an indemnity at maturity of the term. The indemnity shall equal the book value of the assets at the end of the term.

If another customer who wishes to inject natural gas into the distributor's system requests access, during the period covered by the indemnity, to part of all of the MCC freed up by the customer who paid the indemnity, the indemnity may be partially reimbursed by the distributor in accordance with the agreement between the parties.

### 14.5.4 NATURAL GAS PRESSURE, COMPOSITION AND CALORIFIC VALUE

The customer's natural gas must be delivered at a pressure sufficient to allow natural gas to be injected in the distributor's system at the receipt point but shall not exceed the maximum pressure provided in the contract.

The natural gas injected by the customer must meet the TransCanada PipeLines, Canadian Mainline criteria as approved by the Canada Energy Regulator.

If the natural gas injected does not comply with the required standards, the distributor may suspend receipt of the nonconforming gas without notice. The customer shall still be required to fulfill its obligations to the distributor. The customer shall also reimburse the distributor for all costs incurred by the nonconformity of the natural gas.

### 14.5.5 REVISION OF MAXIMUM CONTRACTUAL CAPACITY (MCC)

The MCC may be increased during a contract term if it is economic and operationally possible for the distributor to increase the capacity at the receipt point.

The MCC may not be decreased unless the distributor consents to the transfer of the portion of the MCC the customer wishes to dispose of is transferred to another customer who wishes to inject natural gas into the system.

In all cases, revision of the MCC requires an agreement between the parties.

### 14.5.6 DAILY OVERRUNS OF MAXIMUM CONTRACT CAPACITY (MCC)

A customer who wishes to inject, on a particular day, a natural gas volume that is greater than its MCC must request the distributor's permission beforehand.

If it is operationally possible for the distributor to accept this additional volume of natural gas from the customer, it shall be billed the sum of  $110\% \times 1000$  x the price of the minimum daily obligation, the unit price for the volume injected applicable at the receipt point and the unit price for the volume delivered within the territory applicable to the consumption zone or  $m^3$ the unit price for the volume delivered outside the territory, as the case may be.

If multiple requests to inject additional volumes of natural gas are made concurrently and said volumes exceed the distributor's ability to accept the natural gas, the available capacity shall be prorated according to the excess volumes requested.

### 14.5.7 POSSESSION AND CONTROL

Gas received by the distributor shall be deemed to be in the custody and under the control of the distributor from the time it is received into the distribution system until it is delivered outside of the distribution system.

### 14.5.8 REQUEST FOR NOMINATION

Subject to Article 14.5.6, requests for nomination received before the deadline of the "Timely" nomination window shall be accepted by the distributor and shall be effective the next gas day.

All requests for nomination or revision of nominated volumes received after the "Timely" nomination window can only occur when it is economic and operationally possible for the distributor to agree to it. If applicable, the last request received and accepted cancels the previous.

The request must be submitted in writing to the distributor by email or by fax if need be, by means of the form provided for this purpose. For purposes of this Article, an email is deemed to be written.

A customer must address its request for a nomination or nominated volume revision adjustment to the distributor by the following deadlines:

Nomination Windows	Beginning of Effective Gas Injection	Nomination Deadline
Timely	Next Gas Day at 10:00 EST	Day before at 11:00 ET
Evening	Next Gas Day at 10:00 EST	Day before at 18:00 ET
Intra-Day 1	Current Gas Day at 15:00 EST	Current day at 10:00 ET
Intra-Day 2	Current Gas Day at 19:00 EST	Current day at 14:30 ET
Intra-Day 3	Current Gas Day at 23:00 EST	Current day at 19:00 ET

### 14.5.9 SIMULTANEOUS INJECTION TO THE SAME RECEIPT POINT

### 14.5.9.1 Application

For any receipt point for which multiple customers simultaneously inject natural gas.

### 14.5.9.2 Designation of an Operator

An operator must be designated by customers injecting at a single receipt point.

The operator must provide daily the volumes nominated respectively for each customer of the same receipt point.

Prior to any simultaneous injection to the same receipt point, customers shall inform the distributor, in writing, of the identity of the operator. Customers shall also communicate in writing any change in the identity of the operator.

### 14.5.9.3 Nominated Volumes Reported by the Operator

The nominated volumes reported by the operator will be used to enforce the *Conditions of Service and Tariff* in respect of each customer injecting simultaneously to the same receipt point.

For the purposes of the application of the *Conditions of Service and Tariff,* customers who inject simultaneously to the same receipt point will remain responsible of the information provided to the distributor by the operator.

# 15. CAP-AND-TRADE EMISSION ALLOWANCES SYSTEM

### 15.1 DISTRIBUTOR'S SERVICE

### 15.1.1 APPLICATION

For any customer who withdraws natural gas and did not provide the exemption declaration approved by Énergir's GHG emissions auditor for the period.

### 15.1.2 CAP-AND-TRADE EMISSION ALLOWANCES SYSTEM (CTEAS) SERVICE RATE

### 15.1.2.1 CTEAS Price

For each  $m^3$  of traditional natural gas volume withdrawn, the CTEAS price, as of January 1, 2024, is  $6.958 \phi/m^3$ . The price may be adjusted quarterly to reflect the actual cost of acquisition.

### 15.2 CUSTOMER-PROVIDED SERVICE

### 15.2.1 APPLICATIONS

For any customer who is registered as an emitter in the latest list published by the Minister under Article 35 of the *Regulation respecting a cap-and-trade system for greenhouse gas emission allowances* (chapter Q-2, r. 46.1).

### 15.2.2 RATE

### 15.2.2.1 Service Price

A customer shall not be billed for the price of cap-and-trade emission allowances system distributor's service.

### 16. OTHER APPLICABLE CHARGES

### 16.1.1 DISTRIBUTION SYSTEM CONNECTION CHARGE

The charge provided for in Article 4.3.2 shall be \$300.

### 16.1.2 CHARGE FOR NON-STANDARD CONNECTION

The charge provided for in Article 4.3.3 shall be as follows:

- 1. Where an S6 or S20 metering device is installed, \$50 per linear metre;
- 2. In all other cases, the price determined by the distributor on the basis of an estimate of the costs.

### 16.1.3 CHARGE FOR REDUCTION OF CONNECTION TIME

The charge provided for in Article 4.4.2 shall be as follows:

- \$500 if an S6 or S20 metering device is to be installed in less than 30 business days;
- \$750 if an S40 to S50 metering device is to be installed in less than 40 business days and \$1 000 if an R80 to R450 metering device is to be installed;
- 3. In all other cases, the price shall be determined by the distributor on the basis of an estimate of the costs.

### 16.1.4 CHARGE FOLLOWING REQUEST TO VERIFY A METERING DEVICE

The charge provided for in Article 5.5 shall be as follows:

- 1. \$250 in the case of an S6 or S20 type meter;
- 2. \$580 in the case of an S40 or S50 type meter;
- 3. In all other cases, the price shall be determined by the distributor on the basis of an estimate of the costs.

### 16.1.5 CHARGE FOR NON-HONOURED PAYMENT

The charge provided for in Article 7.2.1 shall be \$25.

### 16.1.6 LATE PAYMENT CHARGE

The late payment charge provided for in Article 9.3 shall be 1.5%.

### 16.1.7 COLLECTION CHARGE

The charge provided for in Article 9.4.2 shall be \$50.

### 16.1.8 RECONNECTION CHARGE

The charge provided for in Articles 2.1.1, 4.4.1 and 9.5 shall be as follows:

- 1. \$225 for customers whose annual volume is less than 10,950 m<sup>3</sup>;
- 2. \$310 for customers whose annual volume is 10,950 m<sup>3</sup> or more.

# SECTION IV EFFECTIVE DATE AND TRANSITIONAL PROVISIONS

# 17. EFFECTIVE DATE AND TRANSITIONAL PROVISIONS

### 17.1 EFFECTIVE DATE

### 17.1.1 APPLICATION

The present *Conditions of Service and Tariff* shall take effect on December 1, 2023 and shall apply to services supplied and volumes withdrawn effective from that date, subject to Article 17.2.1.

### 17.2 Transitional Provisions

### 17.2.1 CUSTOMER GROUPING

Customer grouping for transportation and load balancing services shall be permitted only if the customer grouping opts out from the distributor's transportation service in accordance with Article 17.2.2.  $D_1$  distribution service customers may join the customer grouping for transportation and load balancing services provided the grouping includes a  $D_4$  distribution service customer.

### 17.2.2 PROGRESSIVE WITHDRAWAL FROM THE DISTRIBUTOR'S TRANSPORTATION AND LOAD BALANCING SERVICES

Distribution Rate  $D_3$  and  $D_4$  customers, as well as Distribution Rate  $D_1$  customers whose consumption is at least 75,000 m<sup>3</sup>/year, may request to opt out of the distributor's transportation or load balancing services. Distribution Rate  $D_5$  customers may not opt out of the distributor's transportation service.

Customers wishing to opt out of the distributor's transportation or load balancing services may do so before their written contract expires or during their verbal contract, provided they satisfy the prior notice requirements stipulated in the present *Conditions of Service and Tariff*.

For the purposes of this Article, a customer grouping may ask to opt out from the transportation service or load balancing service if at least one of the customers in the grouping qualifies for the withdrawal as stipulated in the first paragraph above. However, Distribution Rate  $D_5$  customers may not opt out from the distributor's transportation service.

Where a request to opt out of distributor's services has not been submitted, customers shall continue to be billed in accordance with the distributor's services.

### 17.2.3 APPLICATION OF LOAD BALANCING RATE

Where the present *Conditions of Service and Tariff* continue to be applicable after September 30, 2024, the calculation of the parameters and the transposition in Articles 13.1.3 and 13.1.4 shall be modified to recognize the volumes applicable at September 30, 2024.