A. Introduction

- 1. Title: System Operating Limits Methodology for the Planning Horizon
- 2. Number: FAC-010-2.1
- **3. Purpose:** To ensure that System Operating Limits (SOLs) used in the reliable planning of the Bulk Electric System (BES) are determined based on an established methodology or methodologies.
- 4. Applicability
 - **4.1.** Planning Authority
- 5. Effective Date: April 19, 2010

B. Requirements

- **R1.** The Planning Authority shall have a documented SOL Methodology for use in developing SOLs within its Planning Authority Area. This SOL Methodology shall:
 - **R1.1.** Be applicable for developing SOLs used in the planning horizon.
 - **R1.2.** State that SOLs shall not exceed associated Facility Ratings.
 - **R1.3.** Include a description of how to identify the subset of SOLs that qualify as IROLs.
- **R2.** The Planning Authority's SOL Methodology shall include a requirement that SOLs provide BES performance consistent with the following:
 - **R2.1.** In the pre-contingency state and with all Facilities in service, the BES shall demonstrate transient, dynamic and voltage stability; all Facilities shall be within their Facility Ratings and within their thermal, voltage and stability limits. In the determination of SOLs, the BES condition used shall reflect expected system conditions and shall reflect changes to system topology such as Facility outages.
 - **R2.2.** Following the single Contingencies¹ identified in Requirement 2.2.1 through Requirement 2.2.3, the system shall demonstrate transient, dynamic and voltage stability; all Facilities shall be operating within their Facility Ratings and within their thermal, voltage and stability limits; and Cascading or uncontrolled separation shall not occur.
 - **R2.2.1.** Single line to ground or three-phase Fault (whichever is more severe), with Normal Clearing, on any Faulted generator, line, transformer, or shunt device.
 - **R2.2.2.** Loss of any generator, line, transformer, or shunt device without a Fault.
 - **R2.2.3.** Single pole block, with Normal Clearing, in a monopolar or bipolar high voltage direct current system.
 - **R2.3.** Starting with all Facilities in service, the system's response to a single Contingency, may include any of the following:
 - **R2.3.1.** Planned or controlled interruption of electric supply to radial customers or some local network customers connected to or supplied by the Faulted Facility or by the affected area.

¹ The Contingencies identified in R2.2.1 through R2.2.3 are the minimum contingencies that must be studied but are not necessarily the only Contingencies that should be studied.

- **R2.3.2.** System reconfiguration through manual or automatic control or protection actions.
- **R2.4.** To prepare for the next Contingency, system adjustments may be made, including changes to generation, uses of the transmission system, and the transmission system topology.
- **R2.5.** Starting with all Facilities in service and following any of the multiple Contingencies identified in Reliability Standard TPL-003 the system shall demonstrate transient, dynamic and voltage stability; all Facilities shall be operating within their Facility Ratings and within their thermal, voltage and stability limits; and Cascading or uncontrolled separation shall not occur.
- **R2.6.** In determining the system's response to any of the multiple Contingencies, identified in Reliability Standard TPL-003, in addition to the actions identified in R2.3.1 and R2.3.2, the following shall be acceptable:
 - **R2.6.1.** Planned or controlled interruption of electric supply to customers (load shedding), the planned removal from service of certain generators, and/or the curtailment of contracted Firm (non-recallable reserved) electric power Transfers.
- **R3.** The Planning Authority's methodology for determining SOLs, shall include, as a minimum, a description of the following, along with any reliability margins applied for each:
 - **R3.1.** Study model (must include at least the entire Planning Authority Area as well as the critical modeling details from other Planning Authority Areas that would impact the Facility or Facilities under study).
 - **R3.2.** Selection of applicable Contingencies.
 - **R3.3.** Level of detail of system models used to determine SOLs.
 - **R3.4.** Allowed uses of Special Protection Systems or Remedial Action Plans.
 - **R3.5.** Anticipated transmission system configuration, generation dispatch and Load level.
 - **R3.6.** Criteria for determining when violating a SOL qualifies as an Interconnection Reliability Operating Limit (IROL) and criteria for developing any associated IROL T_v.
- **R4.** The Planning Authority shall issue its SOL Methodology, and any change to that methodology, to all of the following prior to the effectiveness of the change:
 - **R4.1.** Each adjacent Planning Authority and each Planning Authority that indicated it has a reliability-related need for the methodology.
 - **R4.2.** Each Reliability Coordinator and Transmission Operator that operates any portion of the Planning Authority's Planning Authority Area.
 - **R4.3.** Each Transmission Planner that works in the Planning Authority's Planning Authority Area.
- **R5.** If a recipient of the SOL Methodology provides documented technical comments on the methodology, the Planning Authority shall provide a documented response to that recipient within 45 calendar days of receipt of those comments. The response shall indicate whether a change will be made to the SOL Methodology and, if no change will be made to that SOL Methodology, the reason why. (Retirement approved by FERC effective January 21, 2014.)

C. Measures

M1. The Planning Authority's SOL Methodology shall address all of the items listed in Requirement 1 through Requirement 3.

M2. The Planning Authority shall have evidence it issued its SOL Methodology and any changes to that methodology, including the date they were issued, in accordance with Requirement 4.

If the recipient of the SOL Methodology provides documented comments on its technical review of that SOL methodology, the Planning Authority that distributed that SOL Methodology shall have evidence that it provided a written response to that commenter within 45 calendar days of receipt of those comments in accordance with Requirement 5. (Retirement approved by FERC effective January 21, 2014.)

D. Compliance

1. Compliance Monitoring Process

1.1. Compliance Monitoring Responsibility

Regional Reliability Organization

1.2. Compliance Monitoring Period and Reset Time Frame

Each Planning Authority shall self-certify its compliance to the Compliance Monitor at least once every three years. New Planning Authorities shall demonstrate compliance through an on-site audit conducted by the Compliance Monitor within the first year that it commences operation. The Compliance Monitor shall also conduct an on-site audit once every nine years and an investigation upon complaint to assess performance.

The Performance-Reset Period shall be twelve months from the last non-compliance.

1.3. Data Retention

The Planning Authority shall keep all superseded portions to its SOL Methodology for 12 months beyond the date of the change in that methodology and shall keep all documented comments on its SOL Methodology and associated responses for three years. In addition, entities found non-compliant shall keep information related to the non-compliance until found compliant. (Deleted text retired-Retirement approved by FERC effective January 21, 2014.)

The Compliance Monitor shall keep the last audit and all subsequent compliance records.

1.4. Additional Compliance Information

The Planning Authority shall make the following available for inspection during an onsite audit by the Compliance Monitor or within 15 business days of a request as part of an investigation upon complaint:

1.4.1 SOL Methodology.

Documented comments provided by a recipient of the SOL Methodology on its technical review of a SOL Methodology, and the associated responses. (Retirement approved by FERC effective January 21, 2014.)

- **1.4.2** Superseded portions of its SOL Methodology that had been made within the past 12 months.
- **1.4.3** Evidence that the SOL Methodology and any changes to the methodology that occurred within the past 12 months were issued to all required entities.

2. Levels of Non-Compliance for Western Interconnection: (To be replaced with VSLs once developed and approved by WECC)

- **2.1. Level 1:** There shall be a level one non-compliance if either of the following conditions exists:
 - **2.1.1** The SOL Methodology did not include a statement indicating that Facility Ratings shall not be exceeded.

- **2.1.2** No evidence of responses to a recipient's comments on the SOL Methodology. (Retirement approved by FERC effective January 21, 2014.)
- **2.2.** Level 2: The SOL Methodology did not include a requirement to address all of the elements in R2.1 through R2.3 and E1.
- **2.3.** Level 3: There shall be a level three non-compliance if any of the following conditions exists:
 - **2.3.1** The SOL Methodology did not include a statement indicating that Facility Ratings shall not be exceeded and the methodology did not include evaluation of system response to one of the three types of single Contingencies identified in R2.2.
 - **2.3.2** The SOL Methodology did not include a statement indicating that Facility Ratings shall not be exceeded and the methodology did not include evaluation of system response to two of the seven types of multiple Contingencies identified in E1.1.
 - **2.3.3** The System Operating Limits Methodology did not include a statement indicating that Facility Ratings shall not be exceeded and the methodology did not address two of the six required topics in R3.
- **2.4.** Level 4: The SOL Methodology was not issued to all required entities in accordance with R4

3. Violation Severity Levels:

Requirement	Lower	Moderate	High	Severe
R1	Not applicable.	The Planning Authority has a documented SOL Methodology for use in developing SOLs within its Planning Authority Area, but it does not address R1.2	The Planning Authority has a documented SOL Methodology for use in developing SOLs within its Planning Authority Area, but it does not address R1.3.	The Planning Authority has a documented SOL Methodology for use in developing SOLs within its Planning Authority Area, but it does not address R1.1. OR The Planning Authority has no documented SOL Methodology for use in developing SOLs within its Planning Authority Area.
R2	The Planning Authority's SOL Methodology is missing one requirement as described in R2.1, R2.2, R2.3, R2.4, R2.5, or R2.6.	The Planning Authority's SOL Methodology is missing two requirements as described in R2.1, R2.2, R2.3, R2.4, R2.5, or R2.6	The Planning Authority's SOL Methodology is missing three requirements as described in R2.1, R2.2, R2.3, R2.4, R2.5, or R2.6.	The Planning Authority's SOL Methodology is missing four or more requirements as described in R2.1, R2.2-, R2.3, R2.4, R2.5, or R2.6
R3	The Planning Authority has a methodology for determining SOLs that includes a description for all but one of the following: R3.1 through R3.6.	The Planning Authority has a methodology for determining SOLs that includes a description for all but two of the following: R3.1 through R3.6.	The Planning Authority has a methodology for determining SOLs that includes a description for all but three of the following: R3.1 through R3.6.	The Planning Authority has a methodology for determining SOLs that is missing a description of four or more of the following: R3.1 through R3.6.
R4	One or both of the following: The Planning Authority issued its SOL Methodology and changes to that methodology to all but one of the required entities. For a change in methodology, the changed methodology was provided up to 30 calendar days after the effectiveness of the change.	One of the following: The Planning Authority issued its SOL Methodology and changes to that methodology to all but one of the required entities AND for a change in methodology, the changed methodology was provided 30 calendar days or more, but less than 60 calendar days after the effectiveness of the change. OR	One of the following: The Planning Authority issued its SOL Methodology and changes to that methodology to all but one of the required entities AND for a change in methodology, the changed methodology was provided 60 calendar days or more, but less than 90 calendar days after the effectiveness of the change. OR	One of the following: The Planning Authority failed to issue its SOL Methodology and changes to that methodology to more than three of the required entities. The Planning Authority issued its SOL Methodology and changes to that methodology to all but one of the required entities AND for a change in methodology, the changed methodology was

Requirement	Lower	Moderate	High	Severe
		The Planning Authority issued its SOL Methodology and changes to that methodology to all but two of the required entities AND for a change in methodology was provided up to 30 calendar days after the effectiveness of the change.	The Planning Authority issued its SOL Methodology and changes to that methodology to all but two of the required entities AND for a change in methodology, the changed methodology was provided 30 calendar days or more, but less than 60 calendar days after the effectiveness of the change. OR The Planning Authority issued its SOL Methodology and changes to that methodology to all but three of the required entities AND for a change in methodology, the changed methodology was provided up to 30 calendar days after the effectiveness of the change.	provided 90 calendar days or more after the effectiveness of the change. OR The Planning Authority issued its SOL Methodology and changes to that methodology to all but two of the required entities AND for a change in methodology, the changed methodology was provided 60 calendar days or more, but less than 90 calendar days after the effectiveness of the change. OR The Planning Authority issued its SOL Methodology and changes to that methodology to all but three of the required entities AND for a change in methodology, the changed methodology was provided 30 calendar days or more, but less than 60 calendar days after the effectiveness of the change. The Planning Authority issued its SOL Methodology and changes to that methodology to all but four of the required entities AND for a change in methodology, the changed methodology was provided up to 30 calendar days after the effectiveness of the change.
R5 (Retirement	The Planning Authority received documented technical comments on its SOL Methodology and	The Planning Authority received documented technical comments on its SOL Methodology and	The Planning Authority received documented technical comments on its SOL Methodology and	The Planning Authority received documented technical comments on its SOL Methodology and

Requirement	Lower	Moderate	High	Severe
approved by FERC effective January 21, 2014.)	provided a complete response in a time period that was longer than 45 calendar days but less than 60 calendar days.	provided a complete response in a time period that was 60 calendar days or longer but less than 75 calendar days.	provided a complete response in a time period that was 75 calendar days or longer but less than 90 calendar days. OR The Planning Authority's response to documented technical comments on its SOL Methodology indicated that a change will not be made, but did not include an explanation of why the change will not be made.	provided a complete response in a time period that was 90 calendar days or longer. OR The Planning Authority's response to documented technical comments on its SOL Methodology did not indicate whether a change will be made to the SOL Methodology.

E. Regional Differences

- **1.** The following Interconnection-wide Regional Difference shall be applicable in the Western Interconnection:
 - **1.1.** As governed by the requirements of R2.5 and R2.6, starting with all Facilities in service, shall require the evaluation of the following multiple Facility Contingencies when establishing SOLs:
 - **1.1.1** Simultaneous permanent phase to ground Faults on different phases of each of two adjacent transmission circuits on a multiple circuit tower, with Normal Clearing. If multiple circuit towers are used only for station entrance and exit purposes, and if they do not exceed five towers at each station, then this condition is an acceptable risk and therefore can be excluded.
 - **1.1.2** A permanent phase to ground Fault on any generator, transmission circuit, transformer, or bus section with Delayed Fault Clearing except for bus sectionalizing breakers or bus-tie breakers addressed in E1.1.7
 - **1.1.3** Simultaneous permanent loss of both poles of a direct current bipolar Facility without an alternating current Fault.
 - **1.1.4** The failure of a circuit breaker associated with a Special Protection System to operate when required following: the loss of any element without a Fault; or a permanent phase to ground Fault, with Normal Clearing, on any transmission circuit, transformer or bus section.
 - **1.1.5** A non-three phase Fault with Normal Clearing on common mode Contingency of two adjacent circuits on separate towers unless the event frequency is determined to be less than one in thirty years.
 - **1.1.6** A common mode outage of two generating units connected to the same switchyard, not otherwise addressed by FAC-010.
 - **1.1.7** The loss of multiple bus sections as a result of failure or delayed clearing of a bus tie or bus sectionalizing breaker to clear a permanent Phase to Ground Fault.
 - **1.2.** SOLs shall be established such that for multiple Facility Contingencies in E1.1.1 through E1.1.5 operation within the SOL shall provide system performance consistent with the following:
 - **1.2.1** All Facilities are operating within their applicable Post-Contingency thermal, frequency and voltage limits.
 - **1.2.2** Cascading does not occur.
 - **1.2.3** Uncontrolled separation of the system does not occur.
 - **1.2.4** The system demonstrates transient, dynamic and voltage stability.
 - **1.2.5** Depending on system design and expected system impacts, the controlled interruption of electric supply to customers (load shedding), the planned removal from service of certain generators, and/or the curtailment of contracted firm (non-recallable reserved) electric power transfers may be necessary to maintain the overall security of the interconnected transmission systems.
 - **1.2.6** Interruption of firm transfer, Load or system reconfiguration is permitted through manual or automatic control or protection actions.

- **1.2.7** To prepare for the next Contingency, system adjustments are permitted, including changes to generation, Load and the transmission system topology when determining limits.
- **1.3.** SOLs shall be established such that for multiple Facility Contingencies in E1.1.6 through E1.1.7 operation within the SOL shall provide system performance consistent with the following with respect to impacts on other systems:
 - **1.3.1** Cascading does not occur.
- **1.4.** The Western Interconnection may make changes (performance category adjustments) to the Contingencies required to be studied and/or the required responses to Contingencies for specific facilities based on actual system performance and robust design. Such changes will apply in determining SOLs.

Version	Date	Action	Change Tracking
1	November 1, 2006	Adopted by Board of Trustees	New
1	November 1, 2006	Fixed typo. Removed the word "each" from the 1 st sentence of section D.1.3, Data Retention.	01/11/07
2	June 24, 2008	Adopted by Board of Trustees; FERC Order 705	Revised
2		Changed the effective date to July 1, 2008 Changed "Cascading Outage" to "Cascading" Replaced Levels of Non-compliance with Violation Severity Levels	Revised
2	January 22, 2010	Updated effective date and footer to April 29, 2009 based on the March 20, 2009 FERC Order	Update
2.1	November 5, 2009	Adopted by the Board of Trustees — errata change Section E1.1 modified to reflect the renumbering of requirements R2.4 and R2.5 from FAC-010-1 to R2.5 and R2.6 in FAC-010-2.	Errata
2.1	April 19, 2010	FERC Approved — errata change Section E1.1 modified to reflect the renumbering of requirements R2.4 and R2.5 from FAC-010- 1 to R2.5 and R2.6 in FAC-010-2.	Errata
2.1	February 7, 2013	R5 and associated elements approved by NERC Board of Trustees for retirement as part of the Paragraph 81 project (Project 2013-02) pending applicable regulatory approval.	

Version History

Standard FAC-010-2.1 — System Operating Limits Methodology for the Planning Horizon

2.1	November 21, 2013	R5 and associated elements approved by FERC for retirement as part of the Paragraph 81 project (Project 2013-02)	
2.1	February 24, 2014	Updated VSLs based on June 24, 2013 approval.	

Standard FAC-010-2.1 — System Operating Limits Methodology for the Planning Horizon Appendix QC-FAC-010-2.1 Provisions specific to the standard FAC-010-2.1 applicable in Québec

This appendix establishes specific provisions for the application of the standard in Québec. Provisions of the standard and of its appendix must be read together for the purposes of understanding and interpretation. Where the standard and appendix differ, the appendix shall prevail.

A. Introduction

- 1. Title: System Operating Limits Methodology for the Planning Horizon
- **2. Number:** FAC-010-2.1
- **3. Purpose:** No specific provision
- 4. Applicability:

Functions

No specific provision

Facilities

This standard only applies to the facilities of the Main Transmission System (RTP)

5. Effective Date:

- 5.1. Adoption of the standard by the Régie de l'énergie: August 2, 2018
- **5.2.** Adoption of the appendix by the Régie de l'énergie: August 2, 2018
- **5.3.** Effective date of the standard and its appendix in Québec: April 1, 2019

Until January 1st, 2022, the Régie specifies that for the purposes of Reliability Standards FAC-010-2.1, FAC-011-2 and FAC-014-2, the calculation and use of System Operating Limits (SOL) for RTP non-Bulk systems which were not planned for performance criteria specified in those standards, in particular, the three-phase fault, must be undertaken as per the Reliability Coordinator's current practice.

B. Requirements

No specific provision

C. Measures

No specific provision

D. Compliance

1. Compliance Monitoring Process

1.1. Compliance Monitoring Responsibility

The Régie de l'énergie is responsible, in Québec, for compliance monitoring with respect to the reliability standard and its appendix that it adopts.

1.2. Compliance Monitoring Period and Reset Time Frame

No specific provision

1.3. Data Retention

No specific provision

1.4. Additional Compliance Information

Standard FAC-010-2.1 — System Operating Limits Methodology for the Planning Horizon Appendix QC-FAC-010-2.1

Provisions specific to the standard FAC-010-2.1 applicable in Québec

No specific provision

2. Levels of Non-Compliance for Western Interconnection

No specific provision

3. Violation Severity Levels

No specific provision

E. Regional Differences

No specific provision

Revision History

Revision	Adoption Date	Action	Change Tracking
0	May 4, 2015	New appendix	New
1	August 2, 2018	Requirement 5 retired and temporary order added to section A5.3 following decision D-2018-101	Revised
2	March 15, 2019	Modification to section A5.3 following decision D-2018-190 and modification to the effective date following decision D- 2019-032	Revised
3	November 28, 2019	Modification to section A5.3 following decision D-2019-162	Revised
4	November 24, 2020	Modification to section A5.3 following decision D-2020-156	Revised