# A. Introduction

## 1. Title: Generator Relay Loadability

# 2. Number: PRC-025-1

**Purpose:** To set load-responsive protective relays associated with generation Facilities at a level to prevent unnecessary tripping of generators during a system disturbance for conditions that do not pose a risk of damage to the associated equipment.

## 3. Applicability:

## **3.1. Functional Entities:**

- **3.1.1** Generator Owner that applies load-responsive protective relays at the terminals of the Elements listed in 3.2, Facilities.
- **3.1.2** Transmission Owner that applies load-responsive protective relays at the terminals of the Elements listed in 3.2, Facilities.
- **3.1.3** Distribution Provider that applies load-responsive protective relays at the terminals of the Elements listed in 3.2, Facilities.
- **3.2.** Facilities: The following Elements associated with Bulk Electric System (BES) generating units and generating plants, including those generating units and generating plants identified as Blackstart Resources in the Transmission Operator's system restoration plan:
  - **3.2.1** Generating unit(s).
  - **3.2.2** Generator step-up (i.e., GSU) transformer(s).
  - **3.2.3** Unit auxiliary transformer(s) (UAT) that supply overall auxiliary power necessary to keep generating unit(s) online.<sup>1</sup>
  - **3.2.4** Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant loads.
  - **3.2.5** Elements utilized in the aggregation of dispersed power producing resources.

## 4. Background:

After analysis of many of the major disturbances in the last 25 years on the North American interconnected power system, generators have been found to have tripped for conditions that did not apparently pose a direct risk to those generators and associated equipment within the time period where the tripping occurred. This tripping has often been determined to have expanded the scope and/or extended the duration of that

<sup>&</sup>lt;sup>1</sup> These transformers are variably referred to as station power, unit auxiliary transformer(s) (UAT), or station service transformer(s) used to provide overall auxiliary power to the generator station when the generator is running. Loss of these transformers will result in removing the generator from service. Refer to the PRC-025-1 Guidelines and Technical Basis for more detailed information concerning unit auxiliary transformers.

disturbance. This was noted to be a serious issue in the August 2003 "blackout" in the northeastern North American continent.<sup>2</sup>

During the recoverable phase of a disturbance, the disturbance may exhibit a "voltage disturbance" behavior pattern, where system voltage may be widely depressed and may fluctuate. In order to support the system during this transient phase of a disturbance, this standard establishes criteria for setting load-responsive protective relays such that individual generators may provide Reactive Power within their dynamic capability during transient time periods to help the system recover from the voltage disturbance. The premature or unnecessary tripping of generators resulting in the removal of dynamic Reactive Power exacerbates the severity of the voltage disturbance, and as a result changes the character of the system disturbance. In addition, the loss of Real Power could initiate or exacerbate a frequency disturbance.

5. Effective Date: See Implementation Plan

# **B. Requirements and Measures**

- **R1.** Each Generator Owner, Transmission Owner, and Distribution Provider shall apply settings that are in accordance with PRC-025-1 Attachment 1: Relay Settings, on each load-responsive protective relay while maintaining reliable fault protection. *[Violation Risk Factor: High] [Time Horizon: Long-Term Planning]*
- M1. For each load-responsive protective relay, each Generator Owner, Transmission Owner, and Distribution Provider shall have evidence (e.g., summaries of calculations, spreadsheets, simulation reports, or setting sheets) that settings were applied in accordance with PRC-025-1 Attachment 1: Relay Settings.

# C. Compliance

## 1. Compliance Monitoring Process

## 1.1. Compliance Enforcement Authority

As defined in the NERC Rules of Procedure, "Compliance Enforcement Authority" means NERC or the Regional Entity in their respective roles of monitoring and enforcing compliance with the NERC Reliability Standards.

## **1.2. Evidence Retention**

The following evidence retention periods identify the period of time an entity is required to retain specific evidence to demonstrate compliance. For instances where the evidence retention period specified below is shorter than the time since the last audit, the Compliance Enforcement Authority (CEA) may ask an entity to provide other evidence to show that it was compliant for the full time period since the last audit.

<sup>&</sup>lt;sup>2</sup> Interim Report: Causes of the August 14th Blackout in the United States and Canada, U.S.-Canada Power System Outage Task Force, November 2003 (http://www.nerc.com/docs/docs/blackout/814BlackoutReport.pdf)

The Generator Owner, Transmission Owner, and Distribution Provider shall keep data or evidence to show compliance as identified below unless directed by its CEA to retain specific evidence for a longer period of time as part of an investigation:

- The Generator Owner, Transmission Owner, and Distribution Provider shall retain evidence of Requirement R1 and Measure M1 for the most recent three calendar years.
- If a Generator Owner, Transmission Owner, or Distribution Provider is found non-compliant, it shall keep information related to the non-compliance until mitigation is complete and approved or for the time specified above, whichever is longer.

The CEA shall keep the last audit records and all requested and submitted subsequent audit records.

## 1.3. Compliance Monitoring and Assessment Processes

**Compliance Audit** 

Self-Certification

Spot Checking

**Compliance Investigation** 

Self-Reporting

Complaint

## 1.4. Additional Compliance Information

None

# **Table of Compliance Elements**

D #	R # Time VRF Horizon	VDE	Violation Severity Levels				
Ν#		VNF	Lower VSL	Moderate VSL	High VSL	Severe VSL	
R1	Long-Term Planning	High	N/A	N/A	N/A	The Generator Owner, Transmission Owner, and Distribution Provider did not apply settings in accordance with <i>PRC-</i> 025-1 – Attachment 1: <i>Relay Settings</i> , on an applied load-responsive protective relay.	

# D. Regional Variances

None.

# E. Interpretations

None.

# F. Associated Documents

NERC System Protection and Control Subcommittee, July 2010, "Power Plant and Transmission System Protection Coordination."

IEEE C37.102-2006, "Guide for AC Generator Protection."

# PRC-025-1 – Attachment 1: Relay Settings

### Introduction

This standard does not require the Generator Owner, Transmission Owner, or Distribution Provider to use any of the protective functions listed in Table 1. Each Generator Owner, Transmission Owner, and Distribution Provider that applies load-responsive protective relays on their respective Elements listed in 3.2, Facilities, shall use one of the following Options in Table 1, Relay Loadability Evaluation Criteria ("Table 1"), to set each load-responsive protective relay element according to its application and relay type. The bus voltage is based on the criteria for the various applications listed in Table 1.

## Generators

Synchronous generator relay pickup setting criteria values are derived from the unit's maximum gross Real Power capability, in megawatts (MW), as reported to the Transmission Planner, and the unit's Reactive Power capability, in megavoltampere-reactive (Mvar), is determined by calculating the MW value based on the unit's nameplate megavoltampere (MVA) rating at rated power factor. If different seasonal capabilities are reported, the maximum capability shall be used for the purposes of this standard.

Asynchronous generator relay pickup setting criteria values (including inverter-based installations) are derived from the site's aggregate maximum complex power capability, in MVA, as reported to the Transmission Planner, including the Mvar output of any static or dynamic reactive power devices.

For the application case where synchronous and asynchronous generator types are combined on a generator step-up transformer or on Elements that connect the generator step-up (GSU) transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant (Elements may also supply generating plant loads.), the pickup setting criteria shall be determined by vector summing the pickup setting criteria of each generator type, and using the bus voltage for the given synchronous generator application and relay type.

## Transformers

Calculations using the GSU transformer turns ratio shall use the actual tap that is applied (i.e., in service) for GSU transformers with deenergized tap changers (DETC). If load tap changers (LTC) are used, the calculations shall reflect the tap that results in the lowest generator bus voltage. When the criterion specifies the use of the GSU transformer's impedance, the nameplate impedance at the nominal GSU transformer turns ratio shall be used.

Applications that use more complex topology, such as generators connected to a multiple winding transformer, are not directly addressed by the criteria in Table 1. These topologies can result in complex power flows, and may require simulation to avoid overly conservative assumptions to simplify the calculations. Entities with these topologies should set their relays in such a way that they do not operate for the conditions being addressed in this standard.

# **Multiple Lines**

Applications that use more complex topology, such as multiple lines that connect the generator step-up (GSU) transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant (Elements may also supply generating plant loads) are not directly addressed by the criteria in Table 1. These topologies can result in complex power flows, and it may require simulation to avoid overly conservative assumptions to simplify the calculations. Entities with these topologies should set their relays in such a way that they do not operate for the conditions being addressed in this standard.

## Exclusions

The following protection systems are excluded from the requirements of this standard:

- 1. Any relay elements that are in service only during start up.
- 2. Load-responsive protective relay elements that are armed only when the generator is disconnected from the system, (e.g., non-directional overcurrent elements used in conjunction with inadvertent energization schemes, and open breaker flashover schemes).
- 3. Phase fault detector relay elements employed to supervise other load-responsive phase distance elements (e.g., in order to prevent false operation in the event of a loss of potential) provided the distance element is set in accordance with the criteria outlined in the standard.
- 4. Protective relay elements that are only enabled when other protection elements fail (e.g., overcurrent elements that are only enabled during loss of potential conditions).
- 5. Protective relay elements used only for Special Protection Systems that are subject to one or more requirements in a NERC or Regional Reliability Standard.
- 6. Protection systems that detect generator overloads that are designed to coordinate with the generator short time capability by utilizing an extremely inverse characteristic set to operate no faster than 7 seconds at 218% of fullload current (e.g., rated armature current), and prevent operation below 115% of full-load current.<sup>3</sup>
- 7. Protection systems that detect transformer overloads and are designed only to respond in time periods which allow an operator 15 minutes or greater to respond to overload conditions.

# Table 1

Table 1 beginning on the next page is structured and formatted to aid the reader with identifying an option for a given load-responsive protective relay.

The first column identifies the application (e.g., synchronous or asynchronous generators, generator step-up transformers, unit auxiliary transformers, Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant

<sup>&</sup>lt;sup>3</sup> IEEE C37.102-2006, "Guide for AC Generator Protection," Section 4.1.1.2.

loads). Dark blue horizontal bars, excluding the header which repeats at the top of each page, demarcate the various applications.

The second column identifies the load-responsive protective relay (e.g., 21, 50, 51, 51V-C, 51V-R, or 67) according to the applied application in the first column. A light blue horizontal bar between the relay types is the demarcation between relay types for a given application. These light blue bars will contain no text.

The third column uses numeric and alphabetic options (i.e., index numbering) to identify the available options for setting load-responsive protective relays according to the application and applied relay type. Another, shorter, light blue bar contains the word "OR," and reveals to the reader that the relay for that application has one or more options (i.e., "ways") to determine the bus voltage and pickup setting criteria in the fourth and fifth column, respectively. The bus voltage column and pickup setting criteria columns provide the criteria for determining an appropriate setting.

The table is further formatted by shading groups of relays associated with asynchronous generator applications. Synchronous generator applications and the unit auxiliary transformer applications are not shaded. Also, intentional buffers were added to the table such that similar options, as possible, would be paired together on a per page basis. Note that some applications may have an additional pairing that might occur on adjacent pages.

Table 1. Relay Loada	bility Evaluation Crite	ria		
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
		la	Generator bus voltage corresponding to 0.95 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	<ul> <li>The impedance element shall be set less than the calculated impedance derived from 115% of:</li> <li>(1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>
		OR		
Synchronous generating unit(s), or Elements utilized in the aggregation of dispersed power producing resources	Phase distance relay (21) – directional toward the Transmission system	lb	Calculated generator bus voltage corresponding to 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer (including the transformer turns ratio and impedance)	The impedance element shall be set less than the calculated impedance derived from 115% of: (1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner, and (2) Reactive Power output – 150% of the MW value, derived from the generator nameplate MVA rating at rated power factor
producing resources		OR		
		lc	Simulated generator bus voltage coincident with the highest Reactive Power output achieved during field- forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	The impedance element shall be set less than the calculated impedance derived from 115% of: (1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner, and (2) Reactive Power output –100% of the maximum gross Mvar output during field-forcing as determined by simulation
		The	e same application continues on the ne	xt page with a different relay type

<sup>&</sup>lt;sup>4</sup> Calculations using the generator step-up (GSU) transformer turns ratio shall use the actual tap that is applied (i.e., in service) for GSU transformers with deenergized tap changers (DETC). If load tap changers (LTC) are used, the calculations shall reflect the tap that results in the lowest generator bus voltage. When the criterion specifies the use of the GSU transformer's impedance, the nameplate impedance at the nominal GSU turns ratio shall be used.

Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria	
		2a	Generator bus voltage corresponding to 0.95 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>	
		OR			
Synchronous generating unit(s), or	Phase time overcurrent relay (51) or (51V-R) – voltage-restrained	overcurrent relay (51) or (51V-R) – voltage-restrained	2b	Calculated generator bus voltage corresponding to 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer (including the transformer turns ratio and impedance)	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>
Elements utilized in the aggregation of		OR			
dispersed power producing resources		2c	Simulated generator bus voltage coincident with the highest Reactive Power output achieved during field- forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	The overcurrent element shall be set greater than 115% of the calculated current derived from: (1) Real Power output – 100% of the gross MW capability reported to the Transmission Planner or, and (2) Reactive Power output –100% of the maximum gross Mvar output during field-forcing as determined by simulation	
			The same application continues with	a different relay type below	
	Phase time overcurrent relay (51V-C) – voltage controlled (Enabled to operate as a function of voltage)		Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	Voltage control setting shall be set less than 75% of the calculated generator bus voltage	

Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
	Phase distance relay (21) – directional toward the Transmission system	4	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	The impedance element shall be set less than the calculated impedance derived from 130% of the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)
Asynchronous				
generating unit(s) (including inverter- based installations), or Elements utilized in the aggregation of	Phase time overcurrent relay (51) or (51V-R) – voltage-restrained	5	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	The overcurrent element shall be set greater than 130% of the calculated current derived from the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)
dispersed power				
producing resources	Phase time overcurrent relay (51V-C) – voltage controlled (Enabled to operate as a function of voltage)	6	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	Voltage control setting shall be set less than 75% of the calculated generator bus voltage

A different application starts on the next page

Table 1. Relay Loada	Table 1. Relay Loadability Evaluation Criteria			
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
				The impedance element shall be set less than the calculated impedance derived from 115% of:
		7a	Generator bus voltage corresponding to 0.95 per unit of the high-side nominal voltage times the turns ratio	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and
	Phase distance relay (21) – directional		of the generator step-up transformer	(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor
	toward the	OR		-
	Transmission system – installed on generator-side of		Calculated generator bus voltage corresponding to 0.85 per unit	The impedance element shall be set less than the calculated impedance derived from 115% of:
Generator step-up transformer(s)	the GSU transformer	7b	nominal voltage on the high-side terminals of the generator step-up	<ul> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>
connected to synchronous generators	If the relay is installed on the high-side of the		transformer (including the transformer turns ratio and impedance)	
	GSU transformer use Option 14	OR		
			Simulated generator bus voltage coincident with the highest Reactive	The impedance element shall be set less than the calculated impedance derived from 115% of:
		7c	Power output achieved during field- forcing in response to a 0.85 per unit	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and
			nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	(2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation
		The	e same application continues on the ne	xt page with a different relay type

Table 1. Relay Loada	bility Evaluation Crite	ria		
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
				The overcurrent element shall be set greater than 115% of the calculated current derived from:
		8a	Generator bus voltage corresponding to 0.95 per unit of the high-side nominal voltage times the turns ratio	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and
			of the generator step-up transformer	(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor
	Phase time overcurrent relay	OR		
	(51) – installed on generator-side of the		Calculated generator bus voltage corresponding to 0.85 per unit	The overcurrent element shall be set greater than 115% of the calculated current derived from:
Generator step-up transformer(s)	GSU transformer If the relay is	8bnominal voltage on the high-side terminals of the generator step-up	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and	
connected to synchronous generators	installed on the high-side of the GSU transformer		transformer (including the transformer turns ratio and impedance)	<ul> <li>MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>
	use Option 15	OR		
			Simulated generator bus voltage coincident with the highest Reactive	The overcurrent element shall be set greater than 115% of the calculated current derived from:
		8c	Power output achieved during field- forcing in response to a 0.85 per unit	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and
			nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	(2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation
		The	e same application continues on the ne	xt page with a different relay type

Table 1. Relay Load	Table 1. Relay Loadability Evaluation Criteria				
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria	
	Phase directional time overcurrent	9a	Generator bus voltage corresponding to 0.95 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>	
	relay (67) – directional toward	OR			
Generator step-up transformer(s) connected to synchronous generators	the Transmission system – installed on generator-side of the GSU transformer If the relay is installed on the high-side of the GSU transformer use Option 16	9b	Calculated generator bus voltage corresponding to 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer (including the transformer turns ratio and impedance)	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 150% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>	
		OR			
		9c	Simulated generator bus voltage coincident with the highest Reactive Power output achieved during field- forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation</li> </ul>	
		· ·	A different application starts on the n	ext page	

Table 1. Relay Loada	bility Evaluation Crite	ria				
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria		
Generator step-up transformer(s) connected to	Phase distance relay (21) – directional toward the Transmission system – installed on generator-side of the GSU transformer If the relay is installed on the high-side of the GSU transformer use Option 17	10	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	The impedance element shall be set less than the calculated impedance derived from 130% of the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)		
asynchronous						
generators only (including inverter- based installations)	Phase time overcurrent relay (51) – installed on generator-side of the GSU transformer If the relay is installed on the high-side of the GSU transformer use Option 18	11	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer for overcurrent relays installed on the low-side	The overcurrent element shall be set greater than 130% of the calculated current derived from the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)		
		The	e same application continues on the ne	xt page with a different relay type		

Table 1. Relay Loada	bility Evaluation Crite	ria				
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria		
Generator step-up transformer(s) connected to asynchronous generators only (including inverter- based installations)	Phase directional time overcurrent relay (67) – directional toward the Transmission system – installed on generator-side of the GSU transformer If the relay is installed on the high-side of the GSU transformer use Option 19	12	Generator bus voltage corresponding to 1.0 per unit of the high-side nominal voltage times the turns ratio of the generator step-up transformer	The overcurrent element shall be set greater than 130% of the calculated current derived from the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)		
			A different application starts belo	ow		
	Phase time overcurrent relay (51) applied at the high-side terminals of the UAT, for which operation of the relay will cause the associated generator to trip.	13a	1.0 per unit of the winding nominal voltage of the unit auxiliary transformer	The overcurrent element shall be set greater than 150% of the calculated current derived from the unit auxiliary transformer maximum nameplate MVA rating		
Unit auxiliary		OR				
transformer(s) (UAT)		13b	Unit auxiliary transformer bus voltage corresponding to the measured current	The overcurrent element shall be set greater than 150% of the unit auxiliary transformer measured current at the generator maximum gross MW capability reported to the Transmission Planner		
			A different application starts on the ne	ext page		

Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria	
	Phase distance relay (21) – directional			The impedance element shall be set less than the calculated impedance derived from 115% of: (1) Real Power output – 100% of the aggregate generation gross	
	toward the	14a	0.85 per unit of the line nominal voltage	MW reported to the Transmission Planner, and	
Elements that	Transmission system – installed on the high-side of the GSU			(2) Reactive Power output – 120% of the aggregate generation MW value, derived from the generator nameplate MVA rating a rated power factor	
connect the GSU	transformer	OR			
transformer(s) to the Transmission system that are used	If the relay is installed on the generator-side of the GSU transformer use Option 7		Simulated line voltage coincident with the highest Reactive Power	The impedance element shall be set less than the calculated impedance derived from 115% of:	
exclusively to export energy directly from		14b	output achieved during field-forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and	
a BES generating unit or generating plant. Elements may also				(2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation	
supply generating plant loads. – connected to synchronous generators	The same application continues on the next page with a different relay type				

Table 1. Relay Loadal	bility Evaluation Crite	ria			
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria	
	Phase overcurrent supervisory element (50) – associated with current-based, communication- assisted schemes where the scheme is capable of tripping	15a	0.85 per unit of the line nominal voltage	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 120% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>	
Elements that	for loss of	OR			
Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant loads. – connected to synchronous generators	for loss of communications installed on the high-side of the GSU transformer or phase time overcurrent relay (51) – installed on the high-side of the GSU transformer If the relay is installed on the generator-side of the GSU transformer use Option 8	1 <i>5</i> b	Simulated line voltage coincident with the highest Reactive Power output achieved during field-forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	The overcurrent element shall be set greater than 115% of the calculated current derived from: (1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and (2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation	
		The	e same application continues on the ne	xt page with a different relay type	

Application	<b>Relay Type</b>	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
	Phase directional overcurrent supervisory element (67) – associated with current-based, communication- assisted schemes where the scheme is	16a	0.85 per unit of the line nominal voltage	<ul> <li>The overcurrent element shall be set greater than 115% of the calculated current derived from:</li> <li>(1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and</li> <li>(2) Reactive Power output – 120% of the aggregate generation MW value, derived from the generator nameplate MVA rating at rated power factor</li> </ul>
	capable of tripping	OR		
Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant load. – connected to synchronous generators		16b	Simulated line voltage coincident with the highest Reactive Power output achieved during field-forcing in response to a 0.85 per unit nominal voltage on the high-side terminals of the generator step-up transformer prior to field-forcing	The overcurrent element shall be set greater than 115% of the calculated current derived from: (1) Real Power output – 100% of the aggregate generation gross MW reported to the Transmission Planner, and (2) Reactive Power output –100% of the aggregate generation maximum gross Mvar output during field-forcing as determined by simulation

# PRC-025-1— Generator Relay Loadability

Table 1. Relay Loadability Evaluation Criteria				
Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant loads. – connected to asynchronous generators only (including inverter- based installations)	Phase distance relay (21) – directional toward the Transmission system– installed on the high-side of the GSU transformer If the relay is installed on the generator-side of the GSU transformer use Option 10	17	1.0 per unit of the line nominal voltage	The impedance element shall be set less than the calculated impedance derived from 130% of the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)
	The same application continues on the next page with a different relay type			

Application	Relay Type	Option	Bus Voltage <sup>4</sup>	Pickup Setting Criteria
Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a BES generating unit or generating plant. Elements may also supply generating plant loads. – connected to asynchronous generators only (including inverter- based installations)	Phase overcurrent supervisory element (50) – associated with current-based, communication- assisted schemes where the scheme is capable of tripping for loss of communications installed on the high-side of the GSU transformer or Phase time overcurrent relay (51) – installed on the high-side of the GSU transformer If the relay is installed on the generator-side of the GSU transformer use Option 11	18	1.0 per unit of the line nominal voltage	The overcurrent element shall be set greater than 130% of the calculated current derived from the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)
	The same application continues on the next page with a different relay type			ext page with a different relay type

# PRC-025-1— Generator Relay Loadability

Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export a BES generating unit connected to asystem installed on the figh-side of the generators only (including inverter- based installations)Phase directional overcurrent supervisory element (67) – associated with current-based, communication- assisted schemes is communications directional toward the Transmission a BES generating unit commentications directional toward the fransmission a BES generating unit communications directional toward the fransmission system installed on the figh-side of the GSU transformer191.0 per unit of the line nominal voltageThe overcurrent element shall be set greater than 130% of the calculated current derived from the maximum aggregate nameplate MVA output at rated power factor (including the Mvar output of any static or dynamic reactive power devices)If the relay is installed on the generator-side of the GSU transformer use Option 12If the relay is installed on the generator-side of the generator-side of the generator side of the generat

# Rationale:

During development of this standard, text boxes were embedded within the standard to explain the rationale for various parts of the standard. Upon BOT approval, the text from the rationale text boxes was moved to this section.

# **Rationale for R1:**

Requirement R1 is a risk-based requirement that requires the responsible entity to be aware of each protective relay subject to the standard and applies an appropriate setting based on its calculations or simulation for the conditions established in Attachment 1.

The criteria established in Attachment 1 represent short-duration conditions during which generation Facilities are capable of providing system reactive resources, and for which generation Facilities have been historically recorded to disconnect, causing events to become more severe.

The term, "while maintaining reliable fault protection" in Requirement R1 describes that the responsible entity is to comply with this standard while achieving their desired protection goals. Refer to the Guidelines and Technical Basis, Introduction, for more information.

Version	Date	Action	Change Tracking
1	August 15, 2013	Adopted by NERC Board of Trustees	New

# Version History

# Standard PRC-025-1 — Generator Relay Loadability

# Appendix QC-PRC-025-1 Provisions specific to the standard PRC-025-1 applicable in Québec

This appendix establishes specific provisions for the application of the standard in Québec. Provisions of the standard and of its appendix must be read together for the purposes of understanding and interpretation. Where the standard and appendix differ, the appendix shall prevail.

#### A. Introduction

- 1. Title: Generator Relay Loadability
- **2.** Number: PRC-025-1

**Purpose:** No specific provision

#### **3.** Applicability:

#### **3.1.** Functional Entity:

No specific provision

- **3.2.** Facilities: The following Elements associated with Main Transmission System (RTP) generating units and generating plants, including those generating units and generating plants identified as Blackstart Resources in the Transmission Operator's system restoration plan:
  - **3.2.1** No specific provision.
  - **3.2.2** No specific provision.
  - **3.2.3** No specific provision.
  - **3.2.4** Elements that connect the GSU transformer(s) to the Transmission system that are used exclusively to export energy directly from a RTP generating unit or generating plant. Elements may also supply generating plant loads.
  - **3.2.5** No specific provision.
- **3.3. Exemptions:** The generating facilities that are not connected to the RTP are exempted from the application of this standard.

#### 4. Background

No specific provision

#### 5. Effective Date:

- 5.1. Adoption of the standard by the Régie de l'énergie: September 27, 2017
- **5.2.** Adoption of the appendix by the Régie de l'énergie: September 27, 2017
- **5.3.** Effective date of the standard and its appendix in Québec: October 1<sup>st</sup>, 2017

Requirements	Applicability	Implementation timeline in Québec	Date of enforcement in Québec
All	For entities affected by the standard in	48 months after adoption of the	October 1 <sup>st</sup> , 2021

#### IMPLEMENTATION PLAN OF PRC-025-1 STANDARD

## Standard PRC-025-1 — Generator Relay Loadability

# Appendix QC-PRC-025-1 Provisions specific to the standard PRC-025-1 applicable in Québec

	which load- responsive protective relays can be set in accordance with the standard	standard by the Régie if the load- responsive protective relays can be set in accordance with the standard	
All	For entities affected by the standard under which the replacement or retirement of load- responsible protective relays can be set in accordance with the standard	72 months after the Régie's adoption of the standard if the replacement or retirement is necessary	October 1 <sup>st</sup> , 2023

## **B.** Requirements and Measures

No specific provision

## C. Compliance

#### 1. Compliance Monitoring Process

## **1.1** Compliance Enforcement Authority

The Régie de l'énergie is responsible, in Québec, for compliance monitoring with respect to the reliability standard and its appendix that it adopts.

#### **1.2** Evidence Retention

No specific provision

# 1.3 Compliance Monitoring and Assessment Process

No specific provision

## **1.4** Additional Compliance Information

No specific provision

#### **Table of Compliance Elements**

No specific provision

#### D. Regional Differences

No specific provision

# Standard PRC-025-1 — Generator Relay Loadability

# Appendix QC-PRC-025-1 Provisions specific to the standard PRC-025-1 applicable in Québec

# E. Interpretations

No specific provision

# F. Associated documents

No specific provision

# PRC-025-1 – Attachment 1: Relays Settings

No specific provision

#### Table 1

No specific provision

#### Rationale

No specific provision

# **Revision History**

Revision	Date	Action	Change Tracking
0	September 27, 2017	New appendix	New